



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.
SECRETARY

MEMORANDUM

DATE: April 8, 2014

TO: Tom Byron, Chief Engineer

FROM: Duane Brautigam, Director, Office of Design
David Sadler, Director, Office of Construction
Tim Lattner, Director, Office of Maintenance

COPIES: Daniel Scheer, State Specifications Engineer

SUBJECT: Mandatory Specification Revision No. 3
July 2014 Workbook

I approve the implementation plan of the subject Specification.

Duane Brautigam	<u>Signature on file</u>	<u>4-8-14</u>
	Director, Office of Design	Date

David Sadler	<u>Signature on file</u>	<u>4-8-14</u>
	Director, Office of Construction	Date

Tim Lattner	<u>Signature on file</u>	<u>4-8-14</u>
	Director, Office of Maintenance	Date



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.
SECRETARY

MEMORANDUM

DATE: April 8, 2014

TO: District Specifications Engineers

FROM: Daniel Scheer, State Specifications Engineer

CC: State Specifications and Estimates Office
Duane Brautigam, Director, Office of Design
David Sadler, Director, Office of Construction
Rudy Powell, State Construction Engineer
Tim Lattner, Director, Office of Maintenance

SUBJECT: MANDATORY SPECIFICATIONS REVISIONS
July 2014 Workbook: Mandatory Revision No. 3

Revise specification packages as described below for the effective letting date as noted:

Specification Number	Heading	Revision Date	Effective Letting Date	Remarks
SP1020905	Maintenance of Traffic.	3-11-14	7-14	New SP. Usage Note: All Jobs.

These specification changes are issued for consistency with Roadway Design Bulletin 14-06, dated March 14, 2014. As per this bulletin, barrier delineators will replace Type C Steady-Burn lights on temporary barrier wall installations.

MAINTENANCE OF TRAFFIC.**(REV 3-11-14) (7-14)**

SUBARTICLE 102-9.5.3 is deleted and the following substituted:

102-9.5.3 Glare Screen (Temporary): Use temporary glare screens listed on the QPL that meet the requirements of Section 990. Furnish, install, maintain, remove and relocate glare screen systems in conjunction with temporary barrier wall at locations identified in the Plans.

Ensure the anchorage of the glare screen to the barrier is capable of safely resisting an equivalent tensile load of 600 pounds per foot of glare screen, with a requirement to use a minimum of three fasteners per barrier section.

When glare screen is utilized on temporary barrier wall, ~~warning lights~~ *barrier delineators* will not be required.

SUBARTICLE 102-11.10 is deleted and the following substituted:

102-11.10 ~~Lights, Temporary, Barrier Wall Mount~~Delineators: The number of ~~Type C steady burn lights~~ *barrier delineators*, ~~mounted~~ *installed* on ~~top of~~ barrier wall, ~~certified as installed~~ used on the project, meeting the requirements of the Design Standards and ~~Section 705 have been properly maintained will be paid for at the Contract unit price for lights temporary, barrier wall mount.~~

SUBARTICLE 102-13.10 is deleted and the following substituted:

102-13.10 ~~Lights, Temporary, Barrier Wall Mount~~Delineators: ~~Price and~~ *No separate* payment will be ~~full compensation for all work and materials~~ *made* for ~~furnishing, installing and maintaining the warning lights mounted~~ *barrier delineators installed on top of* temporary barrier wall. ~~Payment will not be made for lights that are improperly placed or are not working~~ *The cost of furnishing, installing and maintaining the barrier delineators will be included in the cost of the temporary barrier wall.*

SUBARTICLE 102-13.23 is deleted and the following substituted:

102-13.23 Payment Items: Payment will be made under:

Item No. 102- 1-	Maintenance of Traffic - lump sum.
Item No. 102- 2-	Special Detour - lump sum.
Item No. 102- 3-	Commercial Material for Driveway Maintenance - per cubic yard.
Item No. 102- 14-	Traffic Control Officer - per hour.
Item No. 102- 60-	Work Zone Sign - per each per day.
Item No. 102- 61-	Business Sign - each.

Item No. 102- 71-	Barrier Wall - per foot.
Item No. 102- 75-	Temporary Lane Separator - per foot
Item No. 102- 94-	Glare Screen - per foot.
Item No. 102- 73-	Guardrail (Temporary) - per foot.
Item No. 102- 74-	Barricade (Temporary) - per each per day.
Item No. 102- 76-	Arrow Board - per each per day.
Item No. 102- 77-	High Intensity Flashing Lights (Temporary - Type B) - per each per day.
Item No. 102- 78-	Temporary Retroreflective Pavement Markers - each.
Item No. 102- 79-	Lights, Temporary, Barrier Wall Mount - per each per day.
Item No. 102- 81-	Crash Cushion (Gating) (Temporary) - per location.
Item No. 102- 89-	Crash Cushion (Redirective) (Temporary) - per location.
Item No. 102- 99-	Portable Changeable Message Sign (Temporary) - per each per day.
Item No. 102-104-	Temporary Signalization and Maintenance - per intersection per day.
Item No. 102-107-	Temporary Traffic Detection and Maintenance - per intersection per day.
Item No. 102-150-	Portable Regulatory Sign - per each per day.
Item No. 102-150-	Radar Speed Display Unit - per each per day.
Item No. 102-909-	Temporary Raised Rumble Strips - per day.
Item No. 102-911-	Removable Tape (White/Black) - per foot.
Item No. 102-912-	Removable Tape (Yellow) - per foot.
Item No. 710-	Painted Pavement Markings.
Item No. 711-	Thermoplastic Traffic Stripes and Markings.