



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JIM BOXOLD
SECRETARY

May 3, 2016

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section **234**
Proposed Specification: **2340900 Superpave Asphalt Base.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Sherry Valdes of the State Construction Office to remove redundant language. The requirements in the deleted text are included in 9-2.1.2.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to dan.hurtado@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Dan Hurtado, P.E.
State Specifications Engineer

DH/dt

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

SUPERPAVE ASPHALT BASE.
(REV 3-23-16)

ARTICLE 234-9 is deleted and the following substituted:

234-9 Method of Measurement.

The quantity to be paid for will be the plan quantity. For each pay item, the pay area will be adjusted based upon the following formula:

Pay Area = Surface Area (actual tonnage placed/adjusted plan quantity tonnage).

Where: The adjusted plan quantity tonnage is calculated by multiplying the plan quantity square yards (including any Engineer approved quantity revisions) times the spread rate as defined in 234-8.1 and dividing by 2,000 pound./ton, except the pay item's tonnage-weighted average G_{mm} is used instead of the design G_{mm} as defined in 234-8.1.

The pay area shall not exceed 105% of the designed surface area.

Prepare and submit a Certification of Quantities, ~~using the Department's current approved form, for the certified Superpave asphalt base pay item. Submit this certification~~ to the Engineer ~~no later than Twelve O'clock noon Monday after the estimate cut-off or as directed by the Engineer, based on the quantity of asphalt produced and accepted on the Contract. The certification must include the Contract Number, FPID Number, Certification Number, Certification Date, period represented by Certification, and the tons produced for each asphalt pay item~~ in accordance with 9-2.1.2.

SUPERPAVE ASPHALT BASE.**(REV 3-23-16)**

ARTICLE 234-9 is deleted and the following substituted:

234-9 Method of Measurement.

The quantity to be paid for will be the plan quantity. For each pay item, the pay area will be adjusted based upon the following formula:

Pay Area = Surface Area (actual tonnage placed/adjusted plan quantity tonnage).

Where: The adjusted plan quantity tonnage is calculated by multiplying the plan quantity square yards (including any Engineer approved quantity revisions) times the spread rate as defined in 234-8.1 and dividing by 2,000 pound./ton, except the pay item's tonnage-weighted average G_{mm} is used instead of the design G_{mm} as defined in 234-8.1.

The pay area shall not exceed 105% of the designed surface area.

Prepare and submit a Certification of Quantities to the Engineer in accordance with 9-2.1.2.