

# EXPECTED IMPLEMENTATION JULY 2013

## 715 HIGHWAY LIGHTING SYSTEM.

(REV 1-8-12) (FA 2-5-13) (7-13)

SUBARTICLE 715-3.1 (Page 860) is deleted and the following substituted:

**715-3.1 General:** Meet the materials and equipment requirements of Section 992.

ARTICLE 715-9 (Pages 861 – 862) is deleted and the following substituted:

### 715-9 Conduit.

Install conduit at the locations shown in the Plans and in accordance with Section 630.

ARTICLE 715-16 (Pages 863 – 864) is deleted and the following substituted:

### 715-16 Method of Measurement.

The quantities to be paid for will be as follows, completed and accepted:

- (a) Conduit: Payment will be made in accordance with Section 630.
- (b) Luminaire and Truss Arm: The Contract unit price will include the truss arm, luminaire with lamp, and all necessary mounting hardware as indicated in the Plans and the Design Standards.
- (c) Service Point: The Contract unit price will include the service pole, insulators, weatherheads, transformers, enclosures, panel boards, breakers, safety switches, H.O.A. switches, lightning protectors, fuses, photo electric assembly, meter base, and all external and internal conduit and conductors for the service as indicated in the Plans and the Design Standards.
- (d) Light Pole Foundation: The Contract unit price will include the foundation and anchor bolts with lock nuts and washers as indicated in the Plans and the Design Standards.
- (e) Luminaire: The Contract unit price will include the luminaire with lamp and necessary mounting hardware as indicated in the Plans and the Design Standards.
- (f) Pull Box: Payment will be made in accordance with Section 635.
- (g) High Mast Parts: The Contract unit price will include the part specified with all mounting hardware as indicated in the Contract Documents and the Design Standards.
- (h) Frangible Base for Light Pole: The Contract unit price will include the frangible base, attachments, bolts, and washers as indicated in the Plans and the Design Standards.
- (i) Photo Electric Control Assembly: The Contract unit price will include the photo electric control, transformers, conduit, and conductors as indicated in the Plans and the Design Standards.
- (j) Pre-Fab Pilaster: The Contract unit price will include the pilaster and all mounting hardware as indicated in the Plans.
- (k) High Mast Lighting Pole Complete: The Contract unit price will include the pole, luminaires with lamps, lowering system, breakers and anchor bolts with lock nuts and washers, and foundation as indicated in the Plans and the Design Standards.

# EXPECTED IMPLEMENTATION JULY 2013

(l) Conductor: The length, in feet, as indicated in the Plans and the Design

Standards.

(m) Lighting Pole Complete: The Contract unit price will include the pole, internal vibration damping device, truss arm, luminaire with lamp, anchor bolts with lock nuts and washers, frangible base and foundation.

(n) Pole Cable Distribution System: The Contract Unit price will include the surge protector, fuse holders with fuses, waterproof connectors and the waterproof wiring connection to the luminaries.

D

R

A

F

T