

# EXPECTED IMPLEMENTATION JULY 2014

**160 STABILIZING.**  
**(REV 1-9-14) (FA 1-16-14) (7-14)**

SUBARTICLE 160-3.2 is deleted and the following substituted:

**160-3.2 Application of Stabilizing Material:** After substantially completing the roadbed grading operations, determine the type and quantity (if any) of stabilizing material necessary for compliance with the bearing value requirements. Before using any Fossil Fuel Combustion Products (FFCPs), provide documentation, at the preconstruction meeting or no later than 30 days prior to delivery of FFCP's to the project, signed and sealed by the Specialty Engineer that these materials meet the requirements of 403.7047 F.S. Notify the Engineer of the approximate quantity to be added before spreading. When additive stabilizing materials are required, spread the material uniformly over the area to be stabilized.

D

R

A

F

T