



Florida Department of Transportation

**RICK SCOTT**  
**GOVERNOR**

605 Suwannee Street  
Tallahassee, FL 32399-0450

**ANANTH PRASAD, P.E.**  
**SECRETARY**

December 17, 2013

Chad Thompson  
Programs Operations Engineer  
Federal Highway Administration  
545 John Knox Road, Suite 200  
Tallahassee, Florida 32303

Re: State Specifications and Estimates Office  
Section **350**  
Proposed Specification: **3500100 Cement Concrete Pavement.**

Dear Mr. Thompson:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

These changes were proposed by Ghulam Mujtaba to replace the terminology Welded Wire Fabric with Welded Wire Reinforcement.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to SP965DS or daniel.scheer@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Daniel Scheer, P.E.  
State Specifications Engineer

DS/cah  
Attachment

cc: Florida Transportation Builders' Assoc.  
State Construction Engineer

**CEMENT CONCRETE PAVEMENT.****(REV 11-5-13)**

ARTICLE 350-1 is deleted and the following substituted:

**350-1 Description.**

Construct Portland cement concrete pavement in one course, on a prepared subgrade. Use either the fixed-form or the slip-form method of construction. When reinforced cement concrete pavement is specified or required, use concrete reinforced with steel bars or *welded wire reinforcement*~~steel fabric~~, in accordance with details shown in the Plans. The Engineer may require a demonstration of equipment and paving operations.

If any uncontrolled cracks appear during the life of the Contract, remove and replace the cracked concrete at no expense to the Department. Investigate and implement immediate effective solutions to eliminate further cracks, in consultation with, and subject to the approval of the Engineer.

Furnish the following information in the Quality Control Plan (QCP) as required in Section 105:

1. A detailed sequence and schedule of concrete placement operations including, but not limited to, width of pavement to be placed, proposed equipment, production rates, working hours, concrete hauling, and placement, curing, sawing, and sealing methods. Identify backup equipment and the procedures that will be followed in the case of a breakdown of equipment.
2. A method to ensure the proper placement of reinforcing steel, tie bars and dowel bars.
3. A traffic control plan that includes provisions for the placement and maintenance of barriers required to protect the pavement from traffic, for a minimum of 14 days after concrete placement.
4. Defined provisions for adequate lighting for all work done at night, including finishing, curing, and sawing joints.
5. A method for ensuring pavement thickness is met and a consolidation procedure is identified.
6. If forms are to be utilized define the material, dimensions, type, connections, and staking of the forms.
7. Define the procedure for the protection of the fresh concrete pavement from inclement weather.

SUBARTICLE 350-7.2 is deleted and the following substituted:

**350-7.2 ~~Fabric~~Welded Wire Reinforcement:** Place welded wire reinforcement at right angles to the centerline of the pavement and accurately to the position and location shown in the Plans. Lap adjacent sheets of welded wire reinforcement not less than 6 inches. Make the laps only in the longitudinal members.

**CEMENT CONCRETE PAVEMENT.****(REV 11-5-13)**

ARTICLE 350-1 is deleted and the following substituted:

**350-1 Description.**

Construct Portland cement concrete pavement in one course, on a prepared subgrade. Use either the fixed-form or the slip-form method of construction. When reinforced cement concrete pavement is specified or required, use concrete reinforced with steel bars or welded wire reinforcement, in accordance with details shown in the Plans. The Engineer may require a demonstration of equipment and paving operations.

If any uncontrolled cracks appear during the life of the Contract, remove and replace the cracked concrete at no expense to the Department. Investigate and implement immediate effective solutions to eliminate further cracks, in consultation with, and subject to the approval of the Engineer.

Furnish the following information in the Quality Control Plan (QCP) as required in Section 105:

1. A detailed sequence and schedule of concrete placement operations including, but not limited to, width of pavement to be placed, proposed equipment, production rates, working hours, concrete hauling, and placement, curing, sawing, and sealing methods. Identify backup equipment and the procedures that will be followed in the case of a breakdown of equipment.
2. A method to ensure the proper placement of reinforcing steel, tie bars and dowel bars.
3. A traffic control plan that includes provisions for the placement and maintenance of barriers required to protect the pavement from traffic, for a minimum of 14 days after concrete placement.
4. Defined provisions for adequate lighting for all work done at night, including finishing, curing, and sawing joints.
5. A method for ensuring pavement thickness is met and a consolidation procedure is identified.
6. If forms are to be utilized define the material, dimensions, type, connections, and staking of the forms.
7. Define the procedure for the protection of the fresh concrete pavement from inclement weather.

SUBARTICLE 350-7.2 is deleted and the following substituted:

**350-7.2 Welded Wire Reinforcement:** Place welded wire reinforcement at right angles to the centerline of the pavement and accurately to the position and location shown in the Plans. Lap adjacent sheets of welded wire reinforcement not less than 6 inches. Make the laps only in the longitudinal members.