

EXPECTED IMPLEMENTATION JULY 2014

350 CEMENT CONCRETE PAVEMENT. **(REV 11-5-13) (FA 1-2-14) (7-14)**

ARTICLE 350-1 is deleted and the following substituted:

350-1 Description.

Construct Portland cement concrete pavement in one course, on a prepared subgrade. Use either the fixed-form or the slip-form method of construction. When reinforced cement concrete pavement is specified or required, use concrete reinforced with steel bars or welded wire reinforcement, in accordance with details shown in the Plans. The Engineer may require a demonstration of equipment and paving operations.

If any uncontrolled cracks appear during the life of the Contract, remove and replace the cracked concrete at no expense to the Department. Investigate and implement immediate effective solutions to eliminate further cracks, in consultation with, and subject to the approval of the Engineer.

Furnish the following information in the Quality Control Plan (QCP) as required in Section 105:

1. A detailed sequence and schedule of concrete placement operations including, but not limited to, width of pavement to be placed, proposed equipment, production rates, working hours, concrete hauling, and placement, curing, sawing, and sealing methods. Identify backup equipment and the procedures that will be followed in the case of a breakdown of equipment.
2. A method to ensure the proper placement of reinforcing steel, tie bars and dowel bars.
3. A traffic control plan that includes provisions for the placement and maintenance of barriers required to protect the pavement from traffic, for a minimum of 14 days after concrete placement.
4. Defined provisions for adequate lighting for all work done at night, including finishing, curing, and sawing joints.
5. A method for ensuring pavement thickness is met and a consolidation procedure is identified.
6. If forms are to be utilized define the material, dimensions, type, connections, and staking of the forms.
7. Define the procedure for the protection of the fresh concrete pavement from inclement weather.

SUBARTICLE 350-7.2 is deleted and the following substituted:

350-7.2 Welded Wire Reinforcement: Place welded wire reinforcement at right angles to the centerline of the pavement and accurately to the position and location shown in the Plans. Lap adjacent sheets of welded wire reinforcement not less than 6 inches. Make the laps only in the longitudinal members.