## **EXPECTED IMPLEMENTATION JULY 2014**



## 353 CONCRETE PAVEMENT SLAB REPLACEMENT. (REV 12-3-13) (FA 12-16-13) (7-14)

SUBARTICLE 353-9.1 is deleted and the following substituted:

**353-9.1 General:** Construct transverse joints as specified in 350-12 and as shown on the Design Standards, except that dowels bars are installed per 353-9.2. Tie bars will not be placed along the longitudinal joints unless shown in the Contract Documents. Apply a liquid bond breaker recommended by the manufacturer for the intended application to all vertical faces of the adjacent slabs.




Clean and seal joints in accordance with Section 350.

ARTICLE 353-11 is deleted and the following substituted:

## 353-11 Method of Measurement.

The pay quantity for concrete pavement slab replacement, calculated using fieldmeasured horizontal dimensions and thickness of the removed slab, will be the volume, in cubic yards, of calculated concrete volume placed and accepted.

The pay quantity for cleaning and sealing joints will be in accordance with Section 350.



ARTICLE 353-12 is deleted and the following substituted:

## 353-12 Basis of Payment.

Price and payment for concrete pavement slab replacement, will be full compensation for all work specified in this Section and shall include demonstration slab construction, all joint construction, including tie bars and dowels, furnishing of test specimens, and all necessary incidentals.

Price and payment for cleaning and sealing joints will be made in accordance with Section 350.

Payment will be made under:

Item No. 353-70- Concrete Pavement Slab Replacement - per cubic yard.

