

EXPECTED IMPLEMENTATION JULY 2015

D

102 MAINTENANCE OF TRAFFIC. (REV 1-13-15) (FA 1-16-15) (7-15)

SUBARTICLE 102-9.15 is deleted and the following substituted:

102-9.15 Temporary Raised Rumble Strip Set: Furnish, install, maintain, remove, and reinstall temporary raised rumble strips per the manufacturer's recommendations and in accordance with Design Standards, Index No. 603.

The temporary raised rumble strip may be either a removable polymer striping tape or a molded engineered polymer material.

R

SUBARTICLE 102-11.21 is deleted and the following substituted:

102-11.21 Temporary Raised Rumble Strips: The quantity to be paid for will be the number of calendar days, or portions thereof, that temporary raised rumble strips are certified as installed/used on the project within the Contract Time. The number of strips used must meet the requirements of the Design Standards, Index No. 603. No adjustment will be made to the per day measurement for the number of strips or sets used, or for the number of times the sets are relocated.

A

F

T