

# EXPECTED IMPLEMENTATION JULY 2015

## 105 CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS. (REV 9-14-14) (FA 10-21-14) (7-15)

SUBARTICLE 105-8.9 is deleted and the following substituted:

**105-8.9 Prestressed Concrete Plant Quality Control Personnel:** Ensure each prestressed concrete plant has an onsite production manager, an onsite Plant Quality Control Manager, a Plant engineer, and adequate onsite QC inspectors/technicians to provide complete QC inspections and testing.

Ensure the Plant Manager for QC has at least five years of related experience and a current PCI QC personnel Level III certification and a certificate of completion of Section 450 Specification examination. Ensure that the QC inspector/technician has current PCI QC Technician/Inspector Level II certification and a certificate of completion of Section 450 Specification examination.

Ensure that the batch plant operators of the ready mixed concrete batch plants meet the requirements of Section 9.2 of the Materials Manual. Ensure that the batch plant operators of the onsite centrally mixed concrete plants meet the requirements of 105-8.11.2.4.2.

D

R

A

F

T