

EXPECTED IMPLEMENTATION JULY 2015

D

300 PRIME AND TACK COATS.
(REV 11-5-14) (FA 1-22-15) (7-15)

ARTICLE 300-4 is deleted and the following substituted:

300-4 Contractor's Quality Control.

Provide the necessary quality control of the prime and tack coats and application in accordance with the Contract requirements. If the rate of application varies by more than 5% from the rate set by the Engineer or varies beyond the range established in 300-7 or 300-8, immediately make all corrections necessary to bring the spread rate into the acceptable range. The Engineer may take additional measurements at any time. The Engineer will randomly check the Contractor's measurement to verify the spread rate.

R

A

F

T