

# EXPECTED IMPLEMENTATION JULY 2015

## **341 ASPHALT RUBBER MEMBRANE INTERLAYER. (REV 11-7-14) (FA 1-16-15) (7-15)**

ARTICLE 341-1 is deleted and the following substituted:

### **341-1 Description.**

Construct an asphalt rubber membrane interlayer composed of a separate application of asphalt rubber binder covered with a single application of aggregate. Obtain asphalt rubber binder from a plant that is currently on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the requirements of Section 916.

ARTICLE 341-4 is deleted and the following substituted:

### **341-4 Contractor's Quality Control.**

Provide the necessary quality control of the asphalt rubber binder, and interlayer construction in accordance with the Contract requirements. If the rate of application varies by more than 5% from the rate set by the Engineer in accordance with 341-6, immediately make all corrections necessary to bring the spread rate into the acceptable range. The Engineer may take additional measurements at any time. The Engineer will randomly check the Contractor's measurement to verify the spread rate.

SUBARTICLE 341-6.4 is deleted and the following substituted

**341-6.4 Rolling:** In order to ensure maximum embedment of the aggregate, cover the entire width of the mat immediately by traffic rollers. For the first coverage, provide a minimum of three traffic rollers in order to accomplish simultaneous rolling in echelon of the entire width of the spread.

After initial rolling, immediately correct all portions of the completed surface that the Engineer deems defective (not properly covered by aggregates, fat spots, excessive free aggregate, etc.).

Following the first coverage, make additional coverages with traffic rollers as directed by the Engineer.