

EXPECTED IMPLEMENTATION JULY 2015

D

641 PRESTRESSED CONCRETE POLES. (REV 10-29-14) (FA 1-16-15) (7-15)

ARTICLE 641-1 is deleted and the following substituted:

641-1 Description.

Furnish and install prestressed concrete poles as shown in the Plans.

Obtain precast, prestressed concrete poles from a manufacturing plant that is currently on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the requirements of Section 105.

R

Ensure that each pole is constructed and permanently and legibly marked in accordance with Design Standards, Index No. 17725, including the date cast. Concrete closed circuit television (CCTV) poles must be constructed and permanently and legibly marked in accordance with Design Standards, Index No. 18113, unless shown otherwise in the Plans. The marking shall be visible after installation.

Ensure that the shipment of the products to the job site meets the requirements of 450-16.3 and Section 105.

ARTICLE 641-3 is deleted and the following substituted:

A

641-3 Concrete Pole Construction.

Construct concrete poles in accordance with Section 450. Assume responsibility for performance of all quality control testing and inspections required by Sections 346 and 450; however, the PCI personnel certifications are not required. Plant certification, in accordance with Section 105, is not required for plants that manufacture prestressed concrete poles.

F

T