



*Florida Department of Transportation*

RICK SCOTT  
GOVERNOR

605 Suwannee Street  
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.  
SECRETARY

December 31, 2014

Khoa Nguyen  
Director, Office of Technical Services  
Federal Highway Administration  
545 John Knox Road, Suite 200  
Tallahassee, Florida 32303

Re: State Specifications and Estimates Office  
Section **677**  
Proposed Specification: **6770301 Equipment Shelter.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Timothy Ruelke of the State Materials Office (SMO) to revise the language for consistency with changes proposed for Section 105. The Department is revising the Contractor Quality Control (QC) Plan requirements and deleting the narrative portion of the Contractor QC Plan. This change is being made in conjunction with the implementation of the Materials Acceptance and Certification system (MAC), which is replacing the current Laboratory Information Management (LIMS) application.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to SP965DS or [daniel.scheer@dot.state.fl.us](mailto:daniel.scheer@dot.state.fl.us).

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Scheer, P.E.  
State Specifications Engineer

DS/dt

Attachment

cc: Florida Transportation Builders' Assoc.  
State Construction Engineer

**EQUIPMENT SHELTER.**  
**(REV 10-29-14)**

SUBARTICLE 677-3.1 is deleted and the following substituted:

**677-3.1 General:** Provide and detail the equipment shelter installation, including site layout, fencing, and all other features. Submit this drawing for approval prior to the start of construction.

Concrete is to be Class I in accordance with Section 346. Perform concrete structures work in accordance with Section 400. Obtain precast products from a plant that is currently on the Department's ~~list of Producers with accepted Quality Control Programs~~ *Production Facility Listing*. Producers seeking inclusion on the list shall meet the requirements of *Section* 105-3. Submit to the Engineer all permit documents for approval prior to starting the work.

**EQUIPMENT SHELTER.**  
**(REV 10-29-14)**

SUBARTICLE 677-3.1 is deleted and the following substituted:

**677-3.1 General:** Provide and detail the equipment shelter installation, including site layout, fencing, and all other features. Submit this drawing for approval prior to the start of construction.

Concrete is to be Class I in accordance with Section 346. Perform concrete structures work in accordance with Section 400. Obtain precast products from a plant that is currently on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the requirements of Section 105. Submit to the Engineer all permit documents for approval prior to starting the work.