

EXPECTED IMPLEMENTATION JULY 2015

D

677 EQUIPMENT SHELTER.
(REV 10-29-14) (FA 1-16-15) (7-15)

SUBARTICLE 677-3.1 is deleted and the following substituted:

677-3.1 General: Provide and detail the equipment shelter installation, including site layout, fencing, and all other features. Submit this drawing for approval prior to the start of construction.

Concrete is to be Class I in accordance with Section 346. Perform concrete structures work in accordance with Section 400. Obtain precast products from a plant that is currently on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the requirements of Section 105. Submit to the Engineer all permit documents for approval prior to starting the work.

R

A

F

T