

EXPECTED IMPLEMENTATION JULY 2015

929 POZZOLANS AND SLAG. (REV 10-29-14) (FA 1-16-15) (7-15)

SUBARTICLE 929-1.1 is deleted and the following substituted:

929-1.1 General: The cementitious materials supplier shall submit the proposed Quality Control (QC) Plan, certified test reports from an approved independent laboratory acceptable to the State Materials Office, and a sample of the material for Department verification. The Quality Control Program of a cementitious materials supplier shall conform to Section 105. Continuance of Department qualifications is subject to satisfactory results from periodic verification evaluations. A verification sample may be taken at the manufacturer's plant, distribution facility or at the concrete producer's plant.

Upon review of the QC Plan and satisfactory verification of the test results, the plant will be placed on the Department's list of Cementitious Materials Sources with accepted Quality Control Programs. The cementitious materials supplier shall utilize a QC Plan accepted by the State Materials Office. The Department reserves the right to withdraw QC Plan acceptance and to require cementitious material shipments to be individually tested prior to incorporation into Department work. QC Plans may be suspended when the performance of cementitious material is in question, including problems with concrete quality, inconsistent QC data, or failure of QC or verification test results.

Repulable bags may be accepted by the Engineer, provided a successful demonstration by the producer has indicated complete degradation of the repulable bags during the mixing operation and before the mix is discharged.