



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JIM BOXOLD
SECRETARY

December 4, 2015

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section **105**
Proposed Specification: **1050102 Contractor Quality Control General Requirements.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Steve Duke of the State Materials Office to clarify the language relating to items requiring commercial inspection.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to daniel.scheer@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Scheer, P.E.
State Specifications Engineer

DS/dt

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS.
(REV 10-26-15)

SUBARTICLE 105-1.2.3 is deleted and the following substituted:

105-1.2.3 Notification of Placing Order: Order materials sufficiently in advance of their incorporation in the work to allow time for sampling, testing and inspection. Notify the Engineer prior to placing orders for materials.

Submit to the Engineer a fabrication schedule for all items requiring commercial inspection, ~~before or at the preconstruction meeting~~ at least 30 days before beginning fabrication. These items include steel bridge components, ~~overhead cantilevered sign supports with cantilevered arms exceeding 41 feet,~~ moveable bridge components, pedestrian bridges, castings, forgings, structures erected either partially or completely over the travelled roadway or mounted on bridges as overhead traffic signs (some of these may be further classified as cantilevered, overhead trusses, or monotubes) or any other item identified as an item requiring commercial inspection in the Contract Documents.

~~Notify the Engineer at least 30 days before beginning any production and include a production schedule.~~

**CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS.
(REV 10-26-15)**

SUBARTICLE 105-1.2.3 is deleted and the following substituted:

105-1.2.3 Notification of Placing Order: Order materials sufficiently in advance of their incorporation in the work to allow time for sampling, testing and inspection. Notify the Engineer prior to placing orders for materials.

Submit to the Engineer a fabrication schedule for all items requiring commercial inspection at least 30 days before beginning fabrication. These items include steel bridge components, moveable bridge components, pedestrian bridges, castings, forgings, structures erected either partially or completely over the travelled roadway or mounted on bridges as overhead traffic signs (some of these may be further classified as cantilevered, overhead trusses, or monotubes) or any other item identified as an item requiring commercial inspection in the Contract Documents.