

# EXPECTED IMPLEMENTATION JULY 2016

## 105 CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS. (REV 10-26-15) (FA 12-16-15) (7-16)

SUBARTICLE 105-1.2.3 is deleted and the following substituted:

**105-1.2.3 Notification of Placing Order:** Order materials sufficiently in advance of their incorporation in the work to allow time for sampling, testing and inspection. Notify the Engineer prior to placing orders for materials.

Submit to the Engineer a fabrication schedule for all items requiring commercial inspection at least 30 days before beginning fabrication. These items include steel bridge components, moveable bridge components, pedestrian bridges, castings, forgings, structures erected either partially or completely over the travelled roadway or mounted on bridges as overhead traffic signs (some of these may be further classified as cantilevered, overhead trusses, or monotubes) or any other item identified as an item requiring commercial inspection in the Contract Documents.