

# EXPECTED IMPLEMENTATION JULY 2017

## **521 CONCRETE BARRIERS, TRAFFIC RAILING BARRIERS AND PARAPETS. (REV 7-7-16) (FA 10-25-16) (7-17)**

ARTICLE 521-8 is deleted and the following substituted:

### **521-8 Method of Measurement.**

The quantity to be paid for under this Section will be the plan quantity, in feet, completed and accepted. The quantity will be measured along the top of the barrier wall from begin to end station, including transitional and end sections, with no deduction for expansion joints or open joints.

ARTICLE 521-9 is deleted and the following substituted:

### **521-9 Basis of Payment.**

Price and payment will be full compensation for all work specified in this Section, including all reinforcing steel, conduits, materials and incidentals necessary to complete the work.

Payment will be made under:

- |                   |  |
|-------------------|--|
| Item No. 521- 1-  | Median Concrete Barrier Wall - per foot.                             |
| Item No. 521- 5-  | Concrete Traffic Railing Barrier - Bridge - per foot.                |
| Item No. 521- 6-  | Concrete Parapet - per foot.   |
| Item No. 521- 7-  | Concrete Traffic Railing Barrier - Retaining Wall System - per foot. |
| Item No. 521- 8-  | Concrete Traffic Railing – with Junction Slab - per foot.            |
| Item No. 521- 72- | Shoulder Concrete Barrier Wall - per foot.                           |