

FLORIDA DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS for ROAD and BRIDGE
CONSTRUCTION

JANUARY 2015 WORKBOOK
Effective Letting: **JANUARY 1, 2015**

The 2015 Electronic Edition of the Florida Department of Transportation
Standard Specifications is revised as follows:

SPECIAL PROVISIONS	SP0000001	USAGE NOTE	REMARKS
PROPOSAL REQUIREMENTS AND CONDITIONS - EXAMINATION OF CONTRACT DOCUMENTS AND SITE OF WORK. (REV 2-19-14) (FA 2-20-14) (7-14) (1-15) Insert Information Required. Changes to: 2-4.	SP0020400	All Jobs (add contact person and phone no.)	
PREPARATION OF PROPOSALS. (REV 6-22-04) (FA 7-13-04) (7-14) (1-15) Changes to: 2-5.1.	SP0020501AB	A+B Bidding. Use with the approval of the District Construction Engineer. Use with SP0030100AB, SP0030203AB, SP0081300AB and SP0080701AB	
PREPARATION OF PROPOSALS. (REV 2-21-05) (FA 3-31-05) (7-14) (1-15) Insert Information Required. Changes to: 2-5.1.	SP0020501LR	Lane Rental. Use with the approval of the District Construction Engineer. Use with SP0030100LR, SP0081300LR and SP0081300LRDR	
CONSIDERATION OF BIDS – SCOPE ALTERNATES. (REV 4-23-13) (FA 5-14-13) (7-14) (1-15) Changes to: 3-1.	SP0030001	Use with proper authority. *Notify Contracts Office on Transmittal Memo	
AWARD AND EXECUTION OF CONTRACT. (REV 11-5-97) (FA 1-20-98) (7-14) (1-15) Insert Information Required. Changes to: 3-1.	SP0030100AB	A+B Bidding. Use with the approval of the District Construction Engineer. Use with SP0020501AB, SP0030203AB, SP0080701AB and SP0081300AB	

<p>BUDGETARY CONSTRAINTS. (REV 9-26-06) (FA 10-6-06) (7-14)(1-15) Changes to: 3-1.</p>	<p>SP0030100BC</p>	<p>Use at the direction of District Construction in accordance with the Work Program instructions. *Notify Contracts Office on Transmittal Memo</p>	
<p>AWARD AND EXECUTION OF CONTRACT. (REV 12-21-12) (FA 1-10-13) (7-14)(1-15) Insert Information Required. Changes to: 3-1, 3-2.2, 3-5.1.</p>	<p>SP0030100DC</p>	<p>District Let Construction Contracts less than \$250,000 and all Maintenance Contracts, excluding Lump Sum</p>	
<p>AWARD AND EXECUTION OF CONTRACT. (REV 4-11-97) (FA 5-7-97) (7-14)(1-15) Changes to: 3-1.</p>	<p>SP0030100LR</p>	<p>Lane Rental. Use with the approval of the District Construction Engineer. Use with SP0020501LR, SP0081300LR and SP0081300LRDR</p>	
<p>AWARD AND EXECUTION OF CONTRACT. (REV 8-1-00) (7-14)(1-15) Changes to: 3-1.</p>	<p>SP0030100LS</p>	<p>Lump Sum Projects</p>	
<p>AWARD AND EXECUTION OF CONTRACT. (REV 7-26-01) (7-14)(1-15) Insert Information Required. *Contracts Office must approve Changes to: 3-2, 3-6 and 3-7.</p>	<p>SP0030200</p>	<p>When necessary to change standard "Award and Execution". *Contracts Office must approve.</p>	
<p>AWARD OF CONTRACT – A+B BIDDING. (REV 8-22-96) (FA 9-3-96) (7-14)(1-15) Insert Information Required. Changes to: 3-2.</p>	<p>SP0030203AB</p>	<p>A+B Bidding. Use with the approval of the District Construction Engineer. Use with SP0020501AB, SP0030100AB, SP0080701AB and SP0081300AB</p>	

<p>SCOPE OF THE WORK – INTENT OF CONTRACT. (REV 8-19-09) (FA 8-24-09) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 4-1.</p>	<p>SP0040100</p>	<p>All Jobs, excluding Lump Sum. Do not use with SP0040100SLPQ.</p>	
<p>SCOPE OF THE WORK. (REV 8-24-10) (FA 10-8-10) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 4-1, 4-3.1, 4-3.4, 4-3.9.4.</p>	<p>SP0040100LS</p>	<p>All Lump Sum Projects. Do not use with SP0040100SLLS.</p>	
<p>SCOPE OF THE WORK – INTENT AND SCOPE. (REV 8-24-10) (FA 10-8-10) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 4-1, 4-3.1, 4-3.4, 4-3.9.4.</p>	<p>SP0040100SLLS</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt - Streamline Lump Sum. Do not use with SP0040100LS. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>SCOPE OF THE WORK – INTENT AND SCOPE. (REV 9-16-09) (FA 11-9-09) (7-14)(1-15)</p> <p>Insert Information Required. Changes to 4-1, 4-3.1, 4-3.4, 4-3.9.4.</p>	<p>SP0040100SLPQ</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt - Streamline Plan Quantity. Do not use with SP0040100. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>UNFORESEEABLE WORK. (REV 9-28-98) (7-14)(1-15)</p> <p>Changes to: 4-4.</p>	<p>SP0040400</p>	<p>999-25</p>	
<p>CONTROL OF THE WORK. (REV 4-17-14) (7-14)</p> <p>Changes to 5-1.4.5.7.</p>	<p>SP0050104</p>	<p>All Jobs</p>	<p><i>Moved to SS0050104 with FA approval. New SP. Issued as Mandatory No. 6 for the 7-14WB. To include omitted language.</i></p>

<p>CONTROL OF THE WORK. (REV 3-15-02) (7-14)(1-15) Changes to: 5-1.1, 5-2, 5-7.6</p>	<p>SP0050501LS</p>	<p>Lump Sum Projects</p>	
<p>INSPECTION. (REV 2-10-94) (7-14)(1-15) Changes to: 5-9.1.</p>	<p>SP0050901</p>	<p>Long bridge jobs (1500 feet or longer); modify to suit</p>	
<p>CONTROL OF MATERIALS. (REV 8-17-09) (FA 8-24-09) (7-14)(1-15) Changes to: 6-1.</p>	<p>SP0060100LS</p>	<p>Lump Sum Projects</p>	
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC – COMPLIANCE WITH FHWA 1273. (REV 1-2-14) (FA 1-16-14) (7-14)(1-15) Changes to: 7-1.1</p>	<p>SP0070101</p>	<p>All Federal Aid Jobs</p>	
<p>PERMITS PROCURED BY THE DEPARTMENT. (REV 8-7-01) (FA 4-14-05) (7-14)(1-15) Changes to: 7-2.1.</p>	<p>SP0070201A</p>	<p>Jobs with permits procured by DOT</p>	
<p>DISCHARGE TO OR WORK OR STRUCTURES IN NAVIGABLE WATERS OF THE U.S., WATERS OF THE U.S. AND WATERS OF THE STATE. (REV 7-16-09) (FA 7-30-09) (7-14)(1-15) Changes to: 7-2.2</p>	<p>SP0070202</p>	<p>When SWPPP is used. (One or more acre disturbed.)</p>	
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC. (REV 11-13-13) (FA 11-15-13) (7-14)(1-15) Insert Information Required. Changes to: 7-7.1, 7-13.2, 7-13.3.</p>	<p>SP0070701DC</p>	<p>District Let Contracts less than \$250,000 and all Maintenance Contracts.</p>	

<p>LEGAL REQUIREMENTS AND RESPONSIBILITIES TO THE PUBLIC – OPERATIONS WITHIN RAILROAD RIGHT-OF-WAY. (REV 11-5-10) (FA 11-9-10) (7-14)(1-15)</p> <p>Changes to 7-11.5.</p>	<p>SP0071104</p>	<p>Projects Involving CSX Transportation.</p>	
<p>UTILITY WORK. (REV 2-10-94) (7-14)(1-15)</p> <p>Changes to: 7-11.5.3.</p>	<p>SP0071153A</p>	<p>When there are no utility work schedules</p>	
<p>UTILITY SCHEDULES. (REV 8-27-01) (FA 4-14-05) (7-14)(1-15)</p> <p>Changes to: 7-11.5.3.</p>	<p>SP0071153B</p>	<p>When there are utility work schedules</p>	
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC. (REV 4-15-14) (7-14)</p> <p>Changes to 7-13.2, 7-13.4.</p>	<p>SP0071302</p>	<p>All Jobs</p>	<p><i>Moved to SS0070107 with FA approval. New SP. Issued as Mandatory No. 5 for the 7-14WB. To require the Contractor to name utility as an additional insured.</i></p>
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC - WAGE RATES FOR FEDERAL-AID PROJECTS. (REV 12-21-09) (FA 12-28-09) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 7-16.</p>	<p>SP0071600</p>	<p>All Federal Aid Jobs</p>	
<p>EQUAL EMPLOYMENT OPPORTUNITY REQUIREMENTS. (REV 4-25-02) (FA 7-17-02) (7-14)(1-15)</p> <p>Changes to: 7-26.</p>	<p>SP0072600</p>	<p>Non-Federal Aid Projects</p>	
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC – PREFERENCE TO STATE RESIDENTS. (REV 1-13-12) (7-14)(1-15)</p> <p>Changes to: 7-27.</p>	<p>SP0072700</p>	<p>Non-Federal Aid Projects – Construction Projects Only</p>	

<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC – E-VERIFY. (REV 6-13-11) (FA 6-16-11) (7-14)(1-15)</p> <p>Changes to 7-28.</p>	<p>SP0072800</p>	<p>All Jobs</p>	
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC – SCRUTINIZED COMPANIES. (REV 6-17-11) (7-14)(1-15)</p> <p>Changes to Section 7.</p>	<p>SP0072900</p>	<p>All Jobs</p>	
<p>LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC – TITLE VI ASSURANCE – DOT 1050.2, APPENDIX A. (REV 11-12-13) (FA 11-26-13) (3-14)(1-15)</p> <p>Changes to 7-30.</p>	<p>SP0073000</p>	<p>All Federal Aid Jobs</p>	
<p>PROSECUTION AND PROGRESS - SUBMISSION OF WORKING SCHEDULE. (REV 1-11-11) (FA 5-12-11) (7-14)(1-15)</p> <p>Changes to: 8-3.2.</p>	<p>SP0080302A</p>	<p>Use only when CPM is authorized by District Construction Engineer. Do not use with SP0080302DC</p>	
<p>PROSECUTION AND PROGRESS. (REV 6-18-12) (FA 6-18-12) (7-14)(1-15)</p> <p>Changes to: 8-3.2, 8-8, 8-9.1.</p>	<p>SP0080302DC</p>	<p>District Let Contracts (including Lump Sum) less than \$250,000. Do not use with SP0080302A</p>	
<p>PROSECUTION OF WORK - FLEXIBLE START TIME. (REV 2-15-10) (FA 2-17-10) (7-14)(1-15)</p> <p>Insert Information Required. *Contracts Office must be notified Changes to: 8-3.3.</p>	<p>SP0080303A</p>	<p>When called for by the District Construction Engineer or the District Maintenance Engineer/Administrator. *Contracts Office must be notified.</p>	

<p>BEGINNING WORK. (REV 7-10-95) (7-14)(1-15) Insert Information Required. Changes to: 8-3.3.</p>	<p>SP0080303B</p>	<p>When called for by the District Construction Engineer. Use with the approval of the Chief Engineer.</p>	
<p>BEGINNING WORK. (REV 10-22-98) (FA 11-5-98) (7-14)(1-15) Insert Information Required. *Contracts Office must be notified Changes to: 8-3.3.</p>	<p>SP0080303C</p>	<p>When called for by the District Construction Engineer. Use with the approval of the Chief Engineer.</p>	
<p>PROSECUTION OF WORK – PARTNERING. (REV 5-15-12) (FA 5-21-12) (7-14)(1-15) Insert Information Required. *Contracts Office must be notified Changes to: 8-3.6.</p>	<p>SP0080306</p>	<p>999-16*</p>	
<p>PROSECUTION OF WORK - DISPUTES REVIEW BOARD. (REV 1-4-11) (FA 1-21-11) (7-14)(1-15) *Contracts Office must be notified Changes to: 8-3.</p>	<p>SP0080307DRB</p>	<p>999-20 Items*</p>	
<p>PROSECUTION OF WORK – REGIONAL DISPUTES REVIEW BOARD. (REV 1-4-11) (FA 1-21-11) (7-14)(1-15) Changes to: 8-3.</p>	<p>SP0080307RDRB</p>	<p>Jobs without 999-20 Items</p>	
<p>PROSECUTION OF WORK – STATEWIDE DISPUTES REVIEW BOARD. (REV 1-4-11) (FA 1-21-11) (7-14)(1-15) Changes to: 8-3.</p>	<p>SP0080308SDRB</p>	<p>334, 337, 350, 570, 580 or 649 Items</p>	
<p>PROSECUTION AND PROGRESS. (REV 8-1-00) (7-14)(1-15) Changes to: 8-4.1, 8-7-3.1.</p>	<p>SP0080401LS</p>	<p>Lump Sum Projects</p>	

<p>LIMITATIONS OF OPERATIONS – FENCING. (REV 6-17-04) (FA 7-13-04) (7-14)(1-15)</p> <p>Changes to: 8-4.8.</p>	<p>SP0080408</p>	<p>Jobs on Limited Access Highways</p>	
<p>CONTAMINATED MATERIAL – MERCURY-CONTAINING DEVICES AND LAMPS. (REV 11-6-95) (FA 12-27-95) (7-14)(1-15)</p> <p>Insert Information Required. *Insert Hazardous Waste Coordinator and contact number Changes to: 8-4.9.</p>	<p>SP0080409</p>	<p>Jobs with lighting*</p>	
<p>COMPUTATION OF CONTRACT TIME. (REV 12-22-98) (FA 1-19-99) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 8-7.1.</p>	<p>SP0080701A</p>	<p>Use when requested by proper authority, (must be modified)</p>	
<p>COMPUTATION OF CONTRACT TIME. (REV 7-24-96) (FA 9-3-96) (7-14)(1-15)</p> <p>Changes to: 8-7.1.</p>	<p>SP0080701AB</p>	<p>A+B Bidding. Use with approval of the District Construction Engineer. Use with SP0020501AB, SP0030100AB, SP0030203AB and SP0081300AB</p>	
<p>COMPUTATION OF CONTRACT TIME. (REV 2-14-94) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 8-7.1.</p>	<p>SP0080701B</p>	<p>Use when requested by the Chief Engineer (must be modified).</p>	
<p>COMPUTATION OF CONTRACT TIME. (REV 12-22-98) (FA 2-1-99) (7-14)(1-15)</p> <p>Changes to: 8-7.1.</p>	<p>SP0080701C</p>	<p>Use when requested by the District Construction Engineer.</p>	
<p>DAMAGE RECOVERY. (REV 2-4-04) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 8.</p>	<p>SP0081300</p>	<p>Use when requested by District Construction Engineer. (Do not use with Lane Rental)</p>	

<p>PROSECUTION AND PROGRESS. (REV 7-28-97) (1-10)(1-15) Changes to: 8-13.</p>	<p>SP0081300A</p>	<p>All Jobs with Alternative Bidding. Use with the approval of the District Construction Engineer.</p>	
<p>8-13. Incentive – Disincentive for A+B. (REV 7-27-04) (FA 7-28-04) (1-05) Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300AB</p>	<p>A+B Bidding. Use with the approval of the District Construction Engineer. Use with SP0020501AB, SP0030100AB, SP0030203AB and SP0080701AB</p>	
<p>8-13. “Bonus” Payment and Waiver of Contractor Claims. (REV 5-19-04) (FA 7-13-04) (1-05) Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300ABB</p>	<p>A+B Jobs with Bonus. Use with the approval of the District Construction Engineer.</p>	
<p>8-13. “Bonus” Payment and Waiver of Contractor Claims. (REV 7-27-04) (FA 7-28-04) (1-05) Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300B</p>	<p>Bonus (Date Specific). Use with the approval of the District Construction Engineer.</p>	
<p>8-13. “Bonus” Payment and Waiver of Contractor Claims. (REV 7-27-04) (FA 7-28-04) (1-05) Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300BCD</p>	<p>Bonus (Calendar Days). Use with the approval of the District Construction Engineer.</p>	
<p>8-13. Incentive - Disincentive. (REV 7-27-04) (FA 7-28-04) (1-05) Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300ID</p>	<p>Incentive – Disincentive. Use with the approval of the District Construction Engineer. Do not use with SP0081300MID</p>	

<p>8-13. Incentive – Disincentive for Lane Rental Days. (REV 9-25-03) (FA 12-24-03) (7-04)</p> <p>Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300IDLR</p>	<p>Incentive-Disincentive for Lane Rental Days. Use with the approval of the District Construction Engineer. Do not use with SP0081300LR or SP0081300LRDR</p>	
<p>8-13. Liquidated Savings for Early Completion. (REV 5-18-99) (FA 6-10-99) (7-00)</p> <p>Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300LQS</p>	<p>Liquated Savings. Use with the approval of the District Construction Engineer.</p>	
<p>8-13. Pay Adjustment For Fewer-More Lane Rental Days. (REV 4-29-97) (FA 5-7-97) (7-00)</p> <p>Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300LR</p>	<p>Lane Rental. Use with the approval of the District Construction Engineer. Use with SP0020501LR, SP0030100LR, and SP0081300LRDR</p>	
<p>8-13. Damage Recovery. (REV 9-25-03) (FA 12-24-03) (7-04)</p> <p>Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300LRDR</p>	<p>Lane Rental. Use with the approval of the District Construction Engineer. Use with SP0020501LR, SP0030100LR, and SP0081300LR</p>	
<p>8-13. “Bonus” Payment and Waiver of Contractor Claims. (REV 4-12-06) (FA 4-25-06) (1-07)</p> <p>Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300MB</p>	<p>Milestone Bonus. Use with the approval of the District Construction Engineer. Do not use with SP0081300B or SP0081300BCD</p>	
<p>8-13. Incentive - Disincentive. (REV 2-9-06) (FA 4-25-06) (1-07)</p> <p>Insert Information Required. Changes to: 8-13.</p>	<p>SP0081300MID</p>	<p>Milestone Incentive-Disincentive. Use with approval of the District Construction Engineer. Do not use with SP0081300ID</p>	

<p>MEASUREMENT AND PAYMENT. (REV 4-9-14) (FA 4-29-14) (7-141-15)</p> <p>Changes to: 9-1.3, 9-2, 9-3, 9-5.5.2, 9-9, 9-11.</p>	<p>SP0090103LS</p>	<p>Lump Sum Projects. Do not use with SP0090103SLLS.</p>	<p>New SP. <i>Added FA date for Man04.</i> New SP. Issued as Mandatory No. 4 for the 7-14WB. To remove language related to price adjustments for added work.</p>
<p>MEASUREMENT AND PAYMENT. (REV 10-4-132-25-14) (FA 10-15-135-6-14) (7-141-15)</p> <p>Changes to 9-1.3, 9-2, 9-3, 9-5.1, 9-8.1, 9-9, 9-11.</p>	<p>SP0090103SLLS</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt - Streamline Lump Sum. Do not use with SP0090103LS. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	<p><i>New SP. To provide a condition on the Contractor to return all required documents.</i></p>
<p>MEASUREMENT AND PAYMENT. (REV 10-4-132-25-14) (FA 10-15-135-6-14) (7-141-15)</p> <p>Changes to: 9-1.3.2, 9-2, 9-3.2.3, 9-5.1, 9-8.1, 9-9, 9-11.</p>	<p>SP0090103SLPQ</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt - Streamline Plan Quantity. Do not use with SP0090501DC. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	<p><i>New SP. To provide a condition on the Contractor to return all required documents.</i></p>
<p>MEASUREMENT AND PAYMENT. (REV 10-29-08) (FA 1-16-09) (7-14)(1-15)</p> <p>Changes to: 9-5.1, 9-5.4, 9-9.</p>	<p>SP0090501DC</p>	<p>District Let Contracts. Excluding Lump Sum Projects. Do not use with SP0090103SLPQ.</p>	
<p>MEASUREMENT AND PAYMENT. (REV 4-9-14) (7-14)</p> <p>Changes to 9-2.1.1.</p>	<p>SP0090201</p>	<p>All Jobs. Do not use with SP0090103LS, SP0090103SLLS or SP0090103SLPQ.</p>	<p><i>Moved to SS0090201 with FA approval.</i> New SP. Issued as Mandatory No. 4 for the 7-14WB. To remove language related to price adjustments for added work.</p>

<p>MAINTENANCE OF TRAFFIC. (REV 3-19-145-7-14) (7-14)(1-15)</p> <p>Changes to 12-3.2, 102-9.1, 102-9.2, 12-9.5.3, 102-11.5, 102-11.8, 102-11.10, 102-11.22, 102-13.10, 102-13.23.</p>	<p>SP1020302</p>	<p>All Jobs <i>Non Federal Aid Projects</i></p>	<p>New SP. <i>Man03 language moved to SS1020905 with FA approval.</i></p> <p><i>To incorporate language issued by Mandatory Nos. 2 & 3 for the 7-14 WB.</i> To incorporate changes for consistency with RDB 14-06 & to update pay item for rumble strip sets.</p>
<p>ENGINEER'S FIELD OFFICE. (REV 5-8-13) (FA 5-16-13) (7-14)(1-15)</p> <p>Changes to: 109.</p>	<p>SP1090000</p>	<p>109-71 Items</p>	
<p>REMOVAL OF EXISTING STRUCTURES – STRUCTURES TO BE REMOVED. (REV 9-10-07) (FA 2-15-08) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 110-6.1.</p>	<p>SP1100601</p>	<p>Use when requested by the District Construction Engineer. Must have signed agreement with Local Agency receiving the material.</p>	
<p>REMOVAL OF EXISTING STRUCTURES – ASBESTOS CONTAINING MATERIALS (ACM) IDENTIFIED PRIOR TO THE WORK. (REV 1-29-13) (FA 2-15-13) (7-14)(1-15)</p> <p>Changes to: 110-6.6.</p>	<p>SP1100606</p>	<p>Use when areas of Asbestos Abatement are identified in the Plans</p>	
<p>MATERIAL FOR REEF ESTABLISHMENT. (REV 7-10-95) (FA 6-21-99) (7-14)(1-15)</p> <p>Changes to: 110-11.2, 110-12.7.</p>	<p>SP1101102</p>	<p>110-84</p>	
<p>EXCAVATION – IDENTIFIED AREAS OF CONTAMINATION. (REV 1-29-13) (FA 2-15-13) (7-13)(1-15)</p> <p>Changes to: 120-1.</p>	<p>SP1200100A</p>	<p>Use when contaminated areas are delineated in the Plans</p>	

<p>EXCAVATION AND EMBANKMENT – ACCEPTANCE PROGRAM. (REV 9-16-09) (FA 11-9-09) (7-14)(1-15)</p> <p>Changes to: 120-10.3.1</p>	<p>SP1201003SL</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt – Streamline. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>EXCAVATION FOR STRUCTURES AND PIPE – ACCEPTANCE PROGRAM. (REV 9-16-09) (FA 11-9-09) (7-14)(1-15)</p> <p>Change(s) to: 125-9.3.1</p>	<p>SP1250903SL</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt – Streamline. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>STABILIZING – ACCEPTANCE PROGRAM. (REV 9-16-09) (FA 11-9-09) (7-14)(1-15)</p> <p>Changes to: 160-4.2.4</p>	<p>SP1600402SL</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt – Streamline. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>ROCK BASE – ACCEPTANCE PROGRAM. (REV 9-16-09) (FA 11-9-09) (7-14)(1-15)</p> <p>Changes to: 200-7.2.2</p>	<p>SP2000702SL</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt – Streamline. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>GRADED AGGREGATE BASE. (REV 8-8-07) (7-14)(1-15)</p> <p>Changes to: 204.</p>	<p>SP2040000</p>	<p>285 Items Do not use on Interstate Projects</p>	

<p>MILLING OF EXISTING ASPHALT PAVEMENT. (REV 8-31-99) (FA 2-14-00) (7-14)(1-15)</p> <p>Insert Information Required. Changes to: 327-1, 327-6.</p>	<p>SP3270100</p>	<p>When the Plans provide a location for stockpiling milled material. Insert quantity to be retained. Use all, tons, square yards</p>	
<p>MILLING OF EXISTING ASPHALT PAVEMENT. (REV 12-1-93) (7-14)(1-15)</p> <p>Changes to: 327-2.</p>	<p>SP3270200</p>	<p>Use when requested by districts</p>	
<p>PORTLAND CEMENT CONCRETE – ACCEPTANCE SAMPLING AND TESTING. (REV 6-25-10) (FA 7-8-10) (7-14)(1-15)</p> <p>Changes to: 346-9.2.</p>	<p>SP3460902SL</p>	<p>All Contracts less than \$2,000,000 and less than 2,000 tons of asphalt – Streamline. For bridge repair/rehab projects, contact the District Construction Engineer prior to use.</p>	
<p>STRUCTURES FOUNDATIONS. (REV 6-26-12) (7-14)(1-15)</p> <p>Changes to 455-1 through 455-12.</p>	<p>SP4550100DTwTP</p>	<p>Projects with 100% Dynamic Testing of Pile Foundations WITH Test Piles.</p>	
<p>STRUCTURES FOUNDATIONS. (REV 6-26-12) (7-14)(1-15)</p> <p>Changes to 455-1 through 455-12.</p>	<p>SP4550100DTwoT P</p>	<p>Projects with 100% Dynamic Testing of Pile Foundations WITHOUT Test Piles</p>	
<p>INTEGRAL PILE JACKETS. (REV 11-16-11) (FA 12-8-11) (7-14)(1-15)</p> <p>Changes to: 457.</p>	<p>SP4570000</p>	<p>457 Items</p>	

<p>RESETTING GUARDRAIL. (REV 3-6-14) (7-14)</p> <p>Changes to 538</p>	<p>SP5380000</p>	<p>538-1 Items</p>	<p><i>Moved to SS5380000 with FA Approval. New SP. Issued as Mandatory No. 1 for the 7-14WB. Federal Highway Administration Memorandum HSSD, dated May 17, 2010, provided guidance to state transportation agencies on guardrail height for new installations on the National Highway System (NHS). Based on this guidance, the Department will implement a 2'-1" mounting height as our policy for W-beam guardrail systems.</i></p>
<p>LANDSCAPING. (REV 3-15-13) (FA) (7-13)(1-15)</p> <p>Changes to 580.</p>	<p>SP5800000</p>	<p>All Non FA Jobs with Landscaping. Use when requested by the DDE.</p>	
<p>LANDSCAPING. (REV 3-15-13) (7-13)(1-15)</p> <p>Changes to 580.</p>	<p>SP5800000FA</p>	<p>All Federal Aid Jobs with Landscaping. Use when requested by the DDE.</p>	
<p><i>GALVANIZED STEEL POLES, MAST ARMS AND MONOTUBE ASSEMBLIES.</i> (REV 10-13-14) (1-15)</p> <p><i>Changes to 649.</i></p>	<p><i>SP6490000</i></p>	<p><i>All Jobs</i></p>	<p>IMPLEMENTED by MAN02 FOR 1-15WB &eBook.</p>

<p>VEHICULAR TRAFFIC SIGNAL ASSEMBLIES. (REV 10-10-14) (1-15)</p> <p><i>Changes to 650.</i></p>	SP6500000	All Jobs	IMPLEMENTED by MAN02 FOR 1-15WB &eBook.
<p>MAST ARM, SPAN WIRE, AND POLE MOUNTING ASSEMBLIES. (REV 10-10-14) (1-15)</p> <p><i>Changes to 659.</i></p>	SP6590000	All Jobs	IMPLEMENTED by MAN02 FOR 1-15WB &eBook.
<p>TRAFFIC CONTROL SYSTEM AUXILIARIES. (REV 11-5-14) (1-15)</p> <p><i>Changes to 685.</i></p>	SP6850000	685 Items	IMPLEMENTED by MAN03 FOR 1-15WB &eBook.
<p>TRAFFIC MONITORING SITE VEHICLE SENSOR - NON-WEIGHT APPLICATIONS. (REV 1-3-12) (FA 1-27-12) (7-14)(1-15)</p> <p><i>Changes to: 741.</i></p>	SP7410000	741-1 Items	
<p>TRAFFIC MONITORING SITE VEHICLE SPEED/CLASSIFICATION UNIT. (REV 6-16-99) (FA 7-20-99) (7-14)(1-15)</p> <p><i>Changes to: 743.</i></p>	SP7430000	743-70 Items	
<p>TRAFFIC MONITORING SITE SOLAR POWER UNIT. (REV 10-22-10) (FA 11-22-10) (7-14)(1-15)</p> <p><i>Changes to: 744.</i></p>	SP7440000	744-70 Items	
<p>TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY. (REV 1-10-13) (FA 1-15-13) (7-14)(1-15)</p> <p><i>Changes to: 745.</i></p>	SP7450000	745-70 Items	

<p>TRAFFIC MONITORING SITE CABINET. (REV 5-6-08) (FA 10-14-08) (7-14)(1-15)</p> <p>Changes to: 746.</p>	<p>SP7460000</p>	<p>746-7A-BCD Items</p>	
<p>TRAFFIC MONITORING SITE MODEM. (REV 5-20-99) (FA 7-20-99) (7-14)(1-15)</p> <p>Changes to: 747.</p>	<p>SP7470000</p>	<p>747-70 Items</p>	
<p>GENERAL REQUIREMENTS FOR THE EVALUATION OF TRAFFIC MONITORING SITE EQUIPMENT AND MATERIALS. (REV 5-12-99) (FA 7-20-99) (7-14)(1-15)</p> <p>Changes to: 748.</p>	<p>SP7480000</p>	<p>Jobs with Traffic Monitoring Sites</p>	

SUPPLEMENTAL SPECIFICATIONS	SS0000001	USAGE NOTE	REMARKS
<p>001 DEFINITIONS AND TERMS – DEFINITIONS. (REV 3-27-14 6-23-14) (FA 6-5-14 7-2-14) (1-15)</p> <p>Changes to 1-2, 1-3.</p>	<p>SS0010301200</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK.</p> <p>New SS. To remove the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) from the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is part of a planned effort to move material requirements from the MSTCSD to the SSRBC. SS0010300: To include environmental law in the specs language.</p>
<p>005 CONTROL OF THE WORK. (REV 4-17-14) (FA 4-29-14) (1-15)</p> <p>Changes to 5-1.4.5.7.</p>	<p>SS0050104</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK.</p> <p>New SS. To add FA date to Man06 SP0050104 for the 7-14WB.</p>
<p>006 CONTROL OF MATERIALS. (REV 4-13-14) (FA 7-17-14)(1-15)</p> <p>Changes to 006.</p>	<p>SS0060000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK.</p> <p>New SS. To replace references to the Qualified Products List (QPL) with references to the Applied Product List (APL). This is part of the ongoing cooperative effort to consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC).</p>

<p>007 LEGAL REQUIREMENTS AND RESPONSIBILITY TO THE PUBLIC (REV 12-10-133-26-144-15-146-168-1-14) (FA 1-23-144-29-146-5-147-318-12-14) (7-141-15)</p> <p>Changes to <i>7-1.1</i>, 7-1.7, 7-7.2, <i>7-11</i>, 7-13.</p>	<p>SS0070107SS00 <i>70101</i></p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p> <p><i>New SS. Merged in text from SS0070107 & changed dates. To update the web link for the listing of approved insecticides and herbicides for use in Florida.</i></p> <p><i>Merged in text from SS0071101 & changed dates.</i></p> <p><i>To clarify the difference between FDOT's underground facilities and underground utility lines owned by others but permitted by FDOT to be in the right-of-way.</i></p> <p><i>Merged in text from SS0070101& changed name & dates. To include environmental law in the specs language.</i></p> <p><i>Merged in text from SS0071302 & changed dates. Added FA date to Man05 SP0071302 for 7-14WB).</i></p>
<p>008 PROSECUTION AND PROGRESS. (REV 11-26-13) (FA 2-7-14) (7-14)</p> <p>Changes to 8-4.1.</p>	<p>SS0080401</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>009 MEASUREMENT AND PAYMENT. (REV 12-17-134-9-14) (FA 1-28-144-29-14) (7-141-15)</p> <p>Changes to 9-2.1.1.</p>	<p>SS0090201</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p> <p><i>New SS. To add FA date to Man04 SP0090201 for 7-14WB. The mandatory amended the 7-14 SS.</i></p>
<p>009 MEASUREMENT AND PAYMENT. (REV 10-4-13) (FA 10-15-13) (7-14)</p> <p>Changes to 9-8.1</p>	<p>SS0090801</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>102 MAINTENANCE OF TRAFFIC. (REV 1-31-143-11-146-5-148-5-14) (FA 2-7-144-28-147-29-148-21-14) (7-141-15)</p> <p>Changes to <i>102-5.9, 102-9.1, 102-9.1.5, 102-9.5.3, 102-9.9, 102-11.10, 102-11.15, 102-11.21, 102-13.10, 102-13.23.</i></p>	<p>SS1021121SS1020905SS1020509</p> <p>9</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p> <p><i>New SS. Merged in text from SS1020509 & changed name & dates. To clarify the requirements for warning lights and modify the language relating to temporary raised rumble strips for consistency with the Design Standards. Merged in text from SS1020909 & dates. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort. Merged in text from SS1020905 & changed name & dates. Added FA date to Man03 SP1020905 for the 7-14WB.</i></p>
<p><i>102 MAINTENANCE OF TRAFFIC. (REV 7-22-148-19-14) (FA 9-410-14) (1-15)</i></p> <p><i>Changes to 102-6.2, 102-11.3..</i></p>	<p>SS1020602SS1021103</p>	<p>All Jobs</p>	<p><i>New SS. Implemented by Man01 for the 1-15WB and eBook. SS1020602: To add language requiring the Contractor to attend training prior to the release of Department-owned temporary bridging. SS1021103: To clarify payment for Special Detours.</i></p>
<p>110 CLEARING AND GRUBBING. (REV 12-11-13) (FA 1-16-14) (7-14)</p> <p>Changes to 110-11.3.</p>	<p>SS1101103</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p>

<p>120 EXCAVATION AND EMBANKMENT. (REV 12-5-13) (FA 12-16-13) (7-14) Changes to 120.</p>	<p>SS1200000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>125 EXCAVATION FOR STRUCTURES AND PIPE. (REV 12-5-13) (FA 1-24-14) (7-14) Changes to 125-1, 125-9.1.1, 125-9.2.2, 125-11.</p>	<p>SS1250100</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p><i>145 GEOSYNTHETIC REINFORCEMENT. (REV 8-1-14) (FA 7-13-14) (1-15) Changes to 145.</i></p>	<p><i>SS1450000</i></p>	<p><i>All Jobs</i></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To clarify soils testing quality control requirements for geosynthetic reinforced backfill.</i></p>
<p>160 STABILIZING. (REV 1-9-14) (FA 1-16-14) (7-14) Changes to 160-3.1, 160-3.2, 160-4.2.4.</p>	<p>SS1600301</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>200 ROCK BASE. (REV 11-14-137-18-14) (FA 12-3-137-29-14) (7-14-15) Changes to 200-2, 200-6.1, 200-7.2, 200-7.4, 200-11.</p>	<p>SS2000200SS2000702</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To update the language for current Department practice.</i></p>
<p>300 PRIME AND TACK COATS. (REV 12-17-136-19-14) (FA 1-2-147-2-14) (7-14-15) Changes to 300-2.1, 300-2.37, 300-8.</p>	<p>SS3000201 SS3000200</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To update the language for consistency with Department practice.</i></p>
<p>320 HOT MIX ASPHALT - PLANT METHODS AND EQUIPMENT. (REV 10-25-13) (FA 1-2-14) (7-14) Changes to 320-6.3.2.</p>	<p>SS3200603</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>327 MILLING OF EXISTING ASPHALT PAVEMENT. (REV 8-29-13) (FA 11-20-13) (7-14)</p> <p>Changes to 327-3.1.</p>	<p>SS3270301</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>334 SUPERPAVE ASPHALT CONCRETE. (REV 10-25-13 134-28-14) (FA 1-2-14 7-2-14) (7-141-15)</p> <p>Changes to 334-1.4.1, 334-3.2.1, 334-4, 334-5.3.</p>	<p>SS3340104 SS3340400</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To remove the reference to Laboratory Information Management System (LIMS).</i></p>
<p>336 ASPHALT RUBBER BINDER. (REV 11-4-13) (FA 1-2-14) (7-14)</p> <p>Changes to 336-7.</p>	<p>SS3360700</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>337 ASPHALT CONCRETE FRICTION COURSES. (REV 11-4-13 134-28-14 7-2-14) (FA 1-2-14 7-2-14 7-8-14) (7-141-15)</p> <p>Changes to 337-2.1, 337-2.6.</p>	<p>SS3370201</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>Merge in text from SS3370704 & changed dates. To provide clarification for the acronym PLI and for formatting. Merged in text from SS3370802 & changed dates. To update the language for consistency with Department practice.</i></p>
<p>346 PORTLAND CEMENT CONCRETE. (REV 7-17-14) (FA 7-31-14) (1-15)</p> <p><i>Changes to 346.</i></p>	<p>SS3460000</p>	<p><i>All Jobs</i></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To update the language for current Department and industry practice.</i></p>
<p>350 CEMENT CONCRETE PAVEMENT. (REV 11-5-13) (FA 1-2-14) (7-14)</p> <p>Changes to 350-17.2, 350-18.</p>	<p>SS3500100</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>353 CONCRETE PAVEMENT SLAB REPLACEMENT. (REV 1-13-14) (FA 1-16-14) (7-14)</p> <p>Changes to 353-2, 353-9.1, 353-11, 353-12.</p>	<p>SS3530200</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>400 CONCRETE STRUCTURES. (REV 12-16-14 25-147-14-14) (FA 1-28-14 9-147-28-14) (7-141-15)</p> <p>Changes to <i>400-4.4</i>, 400-7.10, <i>400-11.1</i>, 400-16.6, 400-21.3, 400-23.3.</p>	<p>SS4000710SS4000404</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS4000404 & changed name & dates. To require the submittal of shop drawings and calculations for bridge deck overhang falsework under certain geometric conditions.</i> <i>Merged in text from SS4001604 & changed dates. To clarify the requirements for water used in curing concrete for bridge decks.</i> <i>Merged in text from SS4001101 & changed dates. To update the language. The ASTM designation replaces antiquated terminology.</i></p>
<p>410 PRECAST CONCRETE BOX CULVERT. (REV 11-26-13 5-30-14) (FA 12-18-13 8-4-14) (7-141-15)</p> <p>Changes to 410-2.</p>	<p>SS4100200SS4100100</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS4100100 & changed name & date. To update the language for consistency with other sections regarding certification requirements for structures and to add liner repair systems to 410-2.</i></p>
<p>413 SEALING CRACKS AND CONCRETE STRUCTURE SURFACES. (REV 1-22-14) (FA 1-24-14) (7-14)</p> <p>Changes to 413.</p>	<p>SS4130000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>415 REINFORCING STEEL. (REV 11-5-13) (FA 1-15-14) (7-14)</p> <p>Changes to 415-2, 415-6, 415-7.</p>	<p>SS4150200</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p><i>425 INLETS, MANHOLES, AND JUNCTION BOXES. (REV 5-12-14) (FA 8-4-14) (1-15)</i></p> <p><i>Changes to 425.</i></p>	<p>SS4250000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. To update the language for consistency with other sections regarding certification requirements for structures, add liner repair systems to 425-3, and for formatting.</p>
<p>430 PIPE CULVERTS. (REV 11-14-13 8-14-13 5-12-14) (FA 2-18-14 2-29-14 8-4-14) (7-14-15)</p> <p>Changes to <i>430-1, 430-2.1, 430-3, 430-8.1, 430-8.2, 430-9, 430-11.1.</i></p>	<p>SS4300201SS4300100</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. Merged in text from SS4300100 & changed name & dates. To update the language for consistency with other sections regarding certification requirements for structures, add corrugated polypropylene pipe and liner repair systems to 430-2.1, and for formatting. Merged in text from SS4300300 & changed dates. To update the language regarding plan notes.</p>
<p>431 PIPE LINER. (REV 11-14-13) (FA 2-18-14) (7-14)</p> <p>Changes to 431-4.2.5.</p>	<p>SS4310402</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p><i>435 STRUCTURAL PLATE PIPE AND PIPE ARCH CULVERTS. (REV 5-12-14) (FA 8-4-14) (1-15)</i></p> <p><i>Changes to 435.</i></p>	<p>SS4350000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. To update the language for consistency with other sections regarding certification requirements for structures, add liner repair systems to 435-2, and for formatting.</p>

<p>449 PRECAST CONCRETE DRAINAGE PRODUCTS. (REV 11-26-135-12-14) (FA 12-18-138-4-14) (7-141-15)</p> <p>Changes to 449-1, 449-2.</p>	<p>SS4490200SS4490100</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS4490100 & changed names & dates. To update the language for consistency with other sections regarding certification requirements for structures, to add liner repair systems to 449-2, and for formatting.</i></p>
<p>450 PRECAST PRESTRESSED CONCRETE CONSTRUCTION. (REV 12-16-137-21-14) (FA 1-28-148-12-14) (7-141-15)</p> <p>Changes to 450-3.1, 450-11.5, 450-11.6, 450-12.5.3.7.</p>	<p>SS4500301</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS4501105 & changed dates. To clarify the Department's current practice for cutting and protecting prestressing strands</i></p>
<p>455 STRUCTURES FOUNDATIONS. (REV 12-17-132-145-28-148-4-14) (FA 1-22-149-147-28-148-12-14) (7-141-15)</p> <p>Changes to 455.</p>	<p>SS4550000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS4551604 & changed dates. Office to clarify exceptions relating to CSL tubes for drilled shafts for miscellaneous structures. Merged in text from SS4551508 & changed dates. To modify the language for consistency with Department practice. Merged in text from SS4550502 & changed dates. To update the language regarding hydraulic hammers.</i></p>
<p>458 BRIDGE DECK JOINTS. (REV 10-8-13) (FA 12-18-13) (7-14)</p> <p>Changes to 458-2.2.</p>	<p>SS4580202</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>460 STRUCTURAL STEEL AND MISCELLANEOUS METALS. (REV 12-11-138-18-14) (FA 1-8-148-25-14) (7-141-15)</p> <p>Changes to 460-5.1, 460-7.1.3.</p>	<p>SS4600501SS4600000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBook.</u> New SS. Merged in text from SS4600000 & changed name & dates. To update the language for current Department and industry practice.</p>
<p>461 MULTIROTATIONAL BEARINGS. (REV 1-7-14) (FA 1-15-14) (7-14)</p> <p>Changes to 461.</p>	<p>SS4610000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBook.</u></p>
<p>470 TIMBER STRUCTURES. (REV 2-13-14) (FA 2-24-14) (7-14)</p> <p>Changes to 470-12.2.</p>	<p>SS4701202</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBook.</u></p>
<p><i>471 FIBER REINFORCED POLYMER FENDER SYSTEMS. (REV 7-11-14) (FA 9-10-14) (1-1)</i></p> <p><i>Changes to 471.</i></p>	<p><i>SS4710000</i></p>	<p><i>All Jobs</i></p>	<p><i>New SS. Implemented by Man01 for the 1-15WB and eBook. To change the title and update the language for Department and industry practice.</i></p>
<p>520 CONCRETE GUTTER, CURB ELEMENTS, AND TRAFFIC SEPARATOR. (REV 1-7-14) (FA 1-16-14) (7-14)</p> <p>Changes to 520-7, 520-12.</p>	<p>SS5200700</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBook.</u></p>
<p>521 CONCRETE BARRIERS, TRAFFIC RAILING BARRIERS AND PARAPETS. (REV 12-9-13) (FA 12-18-13) (7-14)</p> <p>Changes to 521.</p>	<p>SS5210000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBook.</u></p>
<p>522 CONCRETE SIDEWALK AND DRIVEWAYS. (REV 1-7-14) (FA 1-16-14) (7-14)</p> <p>Changes to 522-7.2.</p>	<p>SS5220702</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBook.</u></p>

<p>523 PATTERNED PAVEMENT. (REV 1-8-14) (FA 1-15-14) (7-14) Changes to 523-1, 523-2.2.</p>	<p>SS5230100</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>534 CONCRETE NOISE WALLS. (REV 1-13-14) (FA 2-18-14) (7-14) Changes to 534.</p>	<p>SS5340000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. To incorporate requirements for perimeter walls as per Engineering and Operations Memorandum 13-03</p>
<p>536 GUARDRAIL. (REV 12-12-13) (2-7-14) (7-14) Changes to 536-5.</p>	<p>SS5360500</p>	<p></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. To delete language that conflicts with the Design Standards, Index No 400, Note 17.</p>
<p><i>538 RESETTING GUARDRAIL. (REV 3-6-14) (FA 3-11-14) (1-15) Changes to 538.</i></p>	<p><i>SS5380000</i></p>	<p><i>All Jobs</i></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Added FA date to SP5380000, issued as Man01 for the 7-14WB.</i></p>
<p>548 RETAINING WALL SYSTEMS. (REV 1-16-14 7-1-14) (FA 1-22-14 7-28-14) (7-14 1-15) Changes to 548.</p>	<p>SS5480000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS5480906 & changed dates. To clarify the required pH testing for walls.</i></p>
<p><i>556 JACK AND BORE. (REV 7-23-14) (FA 7-31-14) (1-15) Changes to 556.</i></p>	<p><i>SS5560000</i></p>	<p><i>All Jobs</i></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To update the certified welder requirement, remove a repetitive ADA reference, and to clarify testing requirements.</i></p>
<p>561 COATING EXISTING STRUCTURAL STEEL. (REV 12-30-14) (FA 1-8-14) (7-14) Changes to 561-10.1, 561-12, 561-13.</p>	<p>SS5611001</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>603 GENERAL REQUIREMENTS FOR TRAFFIC CONTROL SIGNALS AND DEVICES. (REV 1-14-14 23-14 7-18-14) (FA 1-22-14 9-14 8-12-14) (7-14 1-15)</p> <p>Changes to 603.</p>	<p>SS6030000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS6030201 & changed dates. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort. Merged in text from SS6030300 & changed dates. To correct a typo.</i></p>
<p><i>611 ACCEPTANCE PROCEDURES FOR TRAFFIC CONTROL SIGNALS AND DEVICES. (REV 8-5-14) (FA 8-25-14) (1-15)</i></p> <p><i>Changes to 611-2.3.</i></p>	<p><i>SS6110203</i></p>	<p><i>All Jobs</i></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To update specification to reflect the need for submittal information to include DGPS position information and clarify other submittal data requirements.</i></p>
<p>620 TRAFFIC CONTROL SIGNAL AND DEVICE INSTALLATION GROUNDING. (REV 1-30-14) (FA 2-4-14) (7-14)</p> <p>Changes to 620.</p>	<p>SS6200000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>632 SIGNAL CABLE. (REV 2-6-14) (FA 2-18-14) (7-14)</p> <p>Changes to 932-2.</p>	<p>SS6320200</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>633 COMMUNICATION CABLE. (REV 11-18-13) (FA 2-18-14) (7-14)</p> <p>Changes to 633-2.</p>	<p>SS6330203</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>634 SPAN WIRE ASSEMBLY. (REV 11-18-134-14-14) (FA 2-18-145-23-14) (7-141-15)</p> <p>Changes to 634-2.</p>	<p>SS6340200</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. Merged in text from SS6340203 & changed dates. To strengthen the wording of the requirement.</p>
<p>635 PULL, SPLICE, AND JUNCTION BOXES. (REV 11-21-13) (FA 2-4-14) (7-14)</p> <p>Changes to 635-3.2.</p>	<p>SS6350302</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>641 PRESTRESSED CONCRETE POLES. (REV 11-4-138-5-14) (FA 1-8-148-25-14) (7-141-15)</p> <p>Changes to 641-4.2.</p>	<p>SS6410402SS6410000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. Merged in text from SS6410000 & changed name & dates. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p><i>649 GALVANIZED STEEL POLES, MAST ARMS AND MONOTUBE ASSEMBLIES. (REV 5-28-14) (8-12-14) (1-15)</i></p> <p><i>Changes to 649.</i></p>	<p>SS6490000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. To modify the installation requirements for strain poles, mast arms and monotube assemblies</p>

<p>649—GALVANIZED STEEL POLES, MAST ARMS AND MONOTUBE ASSEMBLIES. (REV 5-23-14) (FA 9-4-14) (1-15)</p> <p>Changes to 649.</p>	<p>SS6490000</p>	<p>All Jobs</p>	<p>REPLACED BY SP6500000 - IMPLEMENTED by MAN02 FOR 1-15WB & eBook. <i>New SS6490000.</i> Implemented by Man01 for the 1-15WB and eBook. <i>To change the title and include content for galvanized steel CCTV poles and camera lowering devices previously contained in Section 785 of the Standard Specifications for Road and Bridge Construction (SSRBC). The move of these requirements is part of the Consolidation of Products and Specifications (COPS) effort being undertaken within FDOT Central Office.</i></p>
<p>650—VEHICULAR TRAFFIC SIGNAL ASSEMBLIES. (REV 8-20-14) (FA 9-4-14) (1-15)</p> <p>Changes to 650.</p>	<p>SS6500000</p>	<p>All Jobs</p>	<p>REPLACED BY SP6500000 - IMPLEMENTED by MAN02 FOR 1-15WB & eBook. <i>New SS. Implemented by Man01 for the 1-15WB and eBook.</i> <i>To change the title and consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</i></p>

<p>653 PEDESTRIAN SIGNAL ASSEMBLIES. (REV 9-4-14) (FA 9-16-14) (1-15) Changes to 653.</p>	<p>SS6530000</p>	<p>All Jobs</p>	<p>New SS. Implemented by Man01 for the 1-15WB and eBook. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p>659 MAST ARM, SPAN WIRE, AND POLE MOUNTING ASSEMBLIES. (REV 8-21-14) (FA 9-4-14) (1-15) Changes to 659.</p>	<p>SS6590000</p>	<p>All Jobs</p>	<p>REPLACED BY SP6500000 - IMPLEMENTED by MAN02 FOR 1-15WB & eBook. New SS. Implemented by Man01 for the 1-15WB and eBook. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p>663 SIGNAL PRIORITY AND PREEMPTION SYSTEMS. (REV 1-14-14) (FA 2-4-14) (7-14) New Section 663.</p>	<p>SS6630000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p>

<p>670 TRAFFIC CONTROLLER ASSEMBLIES. (REV 7-29-14) (FA 9-10-14) (1-15) Changes to 670.</p>	<p>SS670000</p>	<p>All Jobs</p>	<p>New SS. Implemented by Man01 for the 1-15WB and eBook. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p>671 TRAFFIC CONTROLLERS. (REV 11-25-13) (FA 1-22-14) (7-14) Changes to 671.</p>	<p>SS6710000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p>
<p>676 TRAFFIC CABINETS. (REV 7-16-14) (FA 9-10-14) (1-15) Changes to 676.</p>	<p>SS6760000</p>	<p>All Jobs</p>	<p>New SS. Implemented by Man01 for the 1-15WB and eBook. To change the title and consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p>677 EQUIPMENT SHELTER. (REV 2-17-14) (FA 2-25-14) (7-14) Changes to 677.</p>	<p>SS6770000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p>

<p>678 TRAFFIC CONTROLLER ACCESSORIES. (REV 5-30-14) (FA 7-14-14) (1-15)</p> <p>Changes to 678.</p>	<p>SS6780000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p> <p>New SS. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p>680 SYSTEM CONTROL EQUIPMENT. (REV 5-5-14) (FA 7-1-14) (1-15)</p> <p>New Section inserted after Section 678.</p>	<p>SS6800000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBook.</p> <p>New SS. NEW SECTION. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>
<p>690 REMOVAL OF EXISTING TRAFFIC CONTROL SIGNALS AND DEVICES. (REV 8-6-14) (FA 8-21-14) (1-15)</p> <p>Section 690 deleted.</p>	<p>SS6900000</p>	<p>All Jobs</p>	<p>New SS. SECTION DELETED. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p> <p>Language in Section 690 will be incorporated in Sections 641, 649, 660, and 670 as applicable.</p>

<p>700 HIGHWAY SIGNING. (REV 1-27-147-18-14) (FA 1-28-147-28-14) (7-14-15)</p> <p>Changes to 700.</p>	<p>SS7000000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. Merged text in from SS7000202 & changed dates. To modify the installation requirements for strain poles, mast arms and monotube assemblies</p>
<p>701 AUDIBLE AND VIBRATORY PAVEMENT MARKINGS. (REV 9-4-13) (FA 10-23-13)(7-14)</p> <p>Changes to 701-4.2, 701-7.</p>	<p>SS7010402</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>702 WET WEATHER PAVEMENT MARKINGS. (REV 9-5-13)5-13-14) (FA 10-23-13)8-26-14) (7-14-15)</p> <p>Changes to 702-4.2, 702-7</p>	<p>SS7020402</p>	<p>All Jobs</p>	<p><u>SECTION DELETED.</u> The Department is moving to a developmental specification which will require continuous wet weather pavement marking retroreflectivity requirements and testing.</p>
<p>709 TRAFFIC STRIPES AND MARKINGS - TWO REACTIVE COMPONENTS. (REV 9-10-13) (FA 10-23-13) (7-14)</p> <p>Changes to 709-7.</p>	<p>SS7090700</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p><i>710 PAINTED PAVEMENT MARKINGS. (REV 5-5-14) (FA 7-28-14) (1-15)</i></p> <p><i>Changes to 710-4.1.</i></p>	<p><i>SS7100401</i></p>	<p><i>All Jobs</i></p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> New SS. To clarify Department policy when using stencils in the application of painted pavement markings.</p>
<p>711 THERMOPLASTIC TRAFFIC STRIPES AND MARKINGS. (REV 9-5-13) (FA 10-23-13) (7-14)</p> <p>Changes to 711-7.</p>	<p>SS7110700</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>713 PERMANENT TAPE TRAFFIC STRIPES AND MARKING. (REV 9-10-135-14-14) (FA 10-23-137-28-14) (7-141-15)</p> <p>Changes to 713-7.</p>	<p>SS7130700SS71 30000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New. SS. Merged in text from SS7130000 & changed name & dates. To delete the requirements for high performance markings. Traffic tape was previously classified as "standard" or "high performance" based on their retroreflectivity and service life. The standard classification was dropped in 2012 leaving only the high performance. Since there is now only one classification for tape and none of the other pavement markings are designated by relative performance, the high performance designation has been deleted.</i></p>
<p>785 INTELLIGENT TRANSPORTATION SYSTEMS —INFRASTRUCTURE. (REV 2-4-146-3-14) (FA 2-7-148-21-14) (7-141-15)</p> <p><i>Changes to 785: Section 785 Deleted</i></p>	<p>SS7850000</p>	<p>All Jobs</p>	<p>SECTION DELETED. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort. Language in Section 785 will be incorporated in Sections 641, 649, and 676 as applicable.</p>
<p>901 COARSE AGGREGATE. (REV 10-16-13) (FA 11-26-13) (7-14)</p> <p>Changes to 901-1.2.</p>	<p>SS9010102</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>914 STABILIZATION MATERIALS. (REV 11-14-13) (FA 11-26-13) (7-14)</p> <p>Changes to 914.</p>	<p>SS9140000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>916 BITUMINOUS MATERIALS. (REV 12-17-136-19-14) (FA 1-8-147-2-14) (7-141-15)</p> <p>Changes to 916.</p>	<p>SS9160000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. To update the language for current Department and industry practice.</i></p>
<p>919 GROUND TIRE RUBBER FOR USE IN ASPHALT RUBBER BINDER. (REV 10-25-13) (FA 1-2-14) (7-14)</p> <p>Changes to 919.</p>	<p>SS9190000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>925 CURING MATERIALS FOR CONCRETE. (REV 1-10-14) (FA 1-23-14) (7-14)</p> <p>Changes to 925.</p>	<p>SS9250000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>926 EPOXY COMPOUNDS. (REV 1-14-14) (FA 1-24-14) (7-14)</p> <p>Changes to 926.</p>	<p>SS9260000</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>
<p>931 METAL ACCESSORY MATERIALS FOR CONCRETE PAVEMENT AND CONCRETE STRUCTURES. (REV 12-9-135-6-14)(FA 1-2-16-137-3-14) (7-141-15)</p> <p>Changes to 931-1.2, 931-3.6, 931-4.</p>	<p>SS9310102SS9310306</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u> <i>New SS. Merged in text from SS9310306 & changed dates. To update an industry standard.</i></p>
<p>932 NONMETALLIC ACCESSORY MATERIALS FOR CONCRETE PAVEMENT AND CONCRETE STRUCTURES. (REV 12-3-13) (FA 1-24-14) (7-14)</p> <p>Changes to 932-1.3.1, 923-1.3.2, 932-2.3.</p>	<p>SS9320103</p>	<p>All Jobs</p>	<p><u>ROLLED INTO THE JANUARY 2015 eBOOK.</u></p>

<p>938 POST-TENSIONING GROUT. (REV 6-9-14) (FA 7-28-14) (1-15) Changes to 938-4.2</p>	<p>SS9380402</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. To modify the language for consistency with current industry practice.</p>
<p>942 PRECAST CONCRETE PIPE GASKETS. (REV 3-6-14) (FA 4-29-14) (1-15) Changes to 942.3</p>	<p>SS9420000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. To change the title of the spec and updated the language.</p>
<p>943 CORRUGATED STEEL PIPE AND PIPE ARCH (INCLUDING UNDERDRAIN). (REV 7-15-14) (FA 8-4-14) (1-15) Changes to 943.</p>	<p>SS9430000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. To add the method for the testing and approval of gaskets, and for formatting.</p>
<p>945 ALUMINUM PIPE, INCLUDING UNDERDRAIN, PIPE ARCH AND STRUCTURAL PLATE PIPE AND PIPE ARCH. (REV 7-15-14) (FA 8-4-14) (1-15) Changes to 945.</p>	<p>SS9450000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. To add the method for the testing of pipe joints and gaskets, and for formatting.</p>
<p>948 OPTIONAL DRAINAGE PRODUCTS AND LINER REPAIR SYSTEMS. (REV 1-27-14 20-14 7-17-14) (FA 2-18-14 7-28-14 148-12-14) (7-141-15) Changes to 948.</p>	<p>SS9480000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. Merged in text from SS9480000 & changed dates. To clarify the requirements for Class II HDPE pipe and to add requirements for polypropylene pipe. Merged in text from SS9480107 & changed dates. To establish the requirement that polyvinyl-chloride (PVC) pipe must be installed within two years of manufacture</p>
<p>960 POST-TENSIONING COMPONENTS. (REV 11-15-13) (FA 1-8-14) (7-14) Changes to 960-2.1.</p>	<p>SS9600201</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK.</p>

<p>971 TRAFFIC MARKING MATERIALS. (REV 1-8-146-26-14) (FA 1-15-148-26-14) (7-14-15)</p> <p>Changes to 971.</p>	<p>SS9710000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. Merged in text from SS9710701 & changed dates. To delete language for wet weather markings, as these markings have been removed from the Standard Specifications. The Department is moving to a developmental specification which will require continuous wet weather pavement marking retroreflectivity requirements and testing.</p>
<p>973 FIBER REINFORCED POLYMER (FRP) COMPOSITE STRUCTURAL MATERIALS. (REV 7-24-14) (FA 8-12-14) (1-15)</p> <p>Changes to 973.</p>	<p>SS9730000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. New SS. To change the title and update the language for industry practice.</p>
<p>985 GEOSYNTHETIC MATERIALS. (REV 9-2-14) (FA 9-10-14 (1-15)</p> <p>Changes to 985.</p>	<p>SS9850000</p>	<p>All Jobs</p>	<p>New SS. Implemented by Man01 for the 1-15WB and eBook. To change the title and update the language in response to industry requests to move geosynthetic materials from the Design Standards to the Approved Product List (APL).</p>
<p>990 TEMPORARY TRAFFIC CONTROL DEVICE MATERIALS. (REV 7-22-14) (FA 7-29-14) (1-15)</p> <p>Changes to 990.</p>	<p>SS9900000</p>	<p>All Jobs</p>	<p>ROLLED INTO THE JANUARY 2015 eBOOK. To consolidate material requirements from the Minimum Specifications for Traffic Control Signals and Devices (MSTCSD) and the Standard Specifications for Road and Bridge Construction (SSRBC). This activity is a planned part of an ongoing specification consolidation effort.</p>

APPENDICES	APENDIC	Header
<p>TECHNICAL SPECIAL PROVISIONS.</p> <p>The following Technical Special Provisions are individually signed and sealed but are included as part of this Specifications Package.</p> <p>Insert # _____</p>	TSPs	Jobs with TSPs