



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JIM BOXOLD
SECRETARY

M E M O R A N D U M

DATE: November 5, 2015

TO: Specification Review Distribution List

FROM: Daniel Scheer, P.E., State Specifications Engineer

SUBJECT: Proposed Specification: **1050102 Contractor Quality Control General Requirements.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Steve Duke of the State Materials Office to clarify the language relating to items requiring commercial inspection.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at

<http://www2.dot.state.fl.us/ProgramManagement/Development/IndustryReview.aspx> .

Comments received after **December 3, 2015**, may not be considered. Your input is encouraged.

DS/dt
Attachment

CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS.
(REV 10-26-15)

SUBARTICLE 105-1.2.3 is deleted and the following substituted:

105-1.2.3 Notification of Placing Order: Order materials sufficiently in advance of their incorporation in the work to allow time for sampling, testing and inspection. Notify the Engineer prior to placing orders for materials.

Submit to the Engineer a fabrication schedule for all items requiring commercial inspection, ~~before or at the preconstruction meeting~~ at least 30 days before beginning fabrication. These items include steel bridge components, ~~overhead cantilevered sign supports with cantilevered arms exceeding 41 feet,~~ moveable bridge components, pedestrian bridges, castings, forgings, structures erected either partially or completely over the travelled roadway or mounted on bridges as overhead traffic signs (some of these may be further classified as cantilevered, overhead trusses, or monotubes) or any other item identified as an item requiring commercial inspection in the Contract Documents.

~~Notify the Engineer at least 30 days before beginning any production and include a production schedule.~~