



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JIM BOXOLD
SECRETARY

M E M O R A N D U M

DATE: November 10, 2016

TO: Specification Review Distribution List

FROM: Dan Hurtado, P.E., State Specifications Engineer

SUBJECT: Proposed Specification: **0060400 Control of Materials.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by John Westphal of the State Construction Office to update the language.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at <http://www2.dot.state.fl.us/ProgramManagement/Development/IndustryReview.aspx> . Comments received after **December 8, 2016**, may not be considered. Your input is encouraged.

DH/dt
Attachment

CONTROL OF MATERIALS.

(REV ~~9-20-16~~11-1-16)

SUBARTICLE 6-4 is deleted and the following substituted:

6-4 Defective Materials.

Materials not meeting the requirements of these Specifications will be considered defective. The Engineer will reject all such materials, whether in place or not. Remove all rejected material immediately from the site of the work and from storage areas, at no expense to the Department.

Do not use material that has been rejected ~~and the defects corrected~~, until the Engineer has approved the material's use. Upon failure to comply promptly with any order of the Engineer made under the provisions of this Article, the Engineer has the authority to have the defective material removed and replaced by other forces and deduct the cost of removal and replacement from any moneys due or to become due the Contractor.

6-4.1 Engineering Analysis: As an exception to the above, within 30 calendar days of the termination of the LOT or rejection of the material, the Contractor may submit to the Engineer a proposed Engineering Analysis Scope of work to the Engineer for an engineering or independent laboratory (as approved by the Engineer) analysis to determine the disposition of the material. The Engineering Analysis Scope must contain at a minimum:

1. Description of the defective materials.
2. Supporting information, testing or inspection reports with nonconformities, pictures, drawings, and accurately dimensioned deficiency maps as necessary. For cracked elements, provide drawings showing the location, average width, depth, length, and termination points of each crack along the surfaces. Provide the distance from each termination point to a fixed reference point on the component, such as beam end or edge of flange.
3. Proposed approach of investigation and analysis.
4. Name and credentials of the proposed Specialty Engineer or Contractor's Engineer of Record who will perform the engineering analysis.
5. Proposed testing laboratories, qualified in accordance with Section 105-7.

Upon approval of the Engineering Analysis Scope by the Engineer, the Specialty Engineer or Contractor's Engineer of Record may perform the engineering analysis as defined in the approved scope and submit a signed and sealed Engineering Analysis Report (EAR) to the Engineer. The EAR must contain at a minimum:

1. The approved Engineering Analysis Scope.
 2. Any investigations performed and the associated results obtained.
 3. Analysis and conclusion.
 4. Proposed disposition of the material, addressing the performance and durability of the proposed action.
- Provide as appropriate:
1. Written evidence of a previously approved comparable deficiency and its repair.
 2. Documented research demonstrating the effectiveness of the proposed repair.
 3. Engineering calculations.

_____ A Specialty Engineer, who is an independent consultant, or the Contractor's Engineer of Record as stated within each individual Section shall perform any such analysis ~~Engineering Analysis. Upon~~ within 45 calendar days of the Engineer's approval of the Engineering Analysis ~~scope of work submitted by the Contractor, complete and submit~~ the Engineering Analysis ~~must be completed and the report must be submitted to the Engineer within 45 calendar days, or other time frame as approved by the Engineer.~~ The EAR ~~Report~~ must be signed and sealed by the Specialty Engineer or the Contractor's Engineer of Record that performed the engineering analysis. The Engineer will determine the final disposition of the material after review of the ~~information submitted by the Contractor~~ EAR. No additional monetary compensation or time extension will be granted for the impact of any such analysis or review.