



*Florida Department of Transportation*

RICK SCOTT  
GOVERNOR

605 Suwannee Street  
Tallahassee, FL 32399-0450

JIM BOXOLD  
SECRETARY

**MEMORANDUM**

**DATE:** November 9, 2016

**TO:** Specification Review Distribution List

**FROM:** Dan Hurtado, P.E., State Specifications Engineer

**SUBJECT:** Proposed Specification: **7010700 Profiled Thermoplastic Pavement Markings.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Daniel Strickland of the State Construction Office to update the language.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at <http://www2.dot.state.fl.us/ProgramManagement/Development/IndustryReview.aspx> . Comments received after **December 7, 2016**, may not be considered. Your input is encouraged.

DH/dt  
Attachment

**PROFILED THERMOPLASTIC PAVEMENT MARKINGS.  
(REV 11-1-16)**

ARTICLE 701-7 is deleted and the following substituted:

**701-7 Observation Period.**

Longitudinal pavement markings, with the exception of bumps, are subject to a 180 day observation period under normal traffic. The observation period will begin with the satisfactory completion and acceptance of the work. The observation period for bumps will be in accordance with the requirements of 701-4.7.

The longitudinal pavement markings shall show no signs of failure due to blistering, excessive cracking, chipping, discoloration, poor adhesion to the pavement, loss of retroreflectivity or vehicular damage. The retroreflectivity shall meet the initial requirements of 701-4.4. The Department reserves the right to check the retroreflectivity anytime prior to the end of the observation period.

Replace, at no expense to the Department, any longitudinal pavement markings that do not perform satisfactorily under traffic during the 180 day observation period.