

**SUMMARY OF PERFORMANCE TURF**

LOCATION STA. TO STA.	SIDE	AREA ID	LENGTH	WIDTH	PERFORMANCE TURF		PERFORMANCE TURF (SOD)		DESIGN NOTES	CONSTRUCTION REMARKS
					0570	1 1	0570	1 2		
					SY		SY			
					P	F	P	F		
<b>NB 1-00</b>										
570+00.00 - 580+62.00	Med.		1062.0	1.3				157		
570+00.00 - 574+57.00	Rt.		457.0	1.3				68		
570+00.00 - 586+37.00	Rt.	32596					6184			
570+00.00 - 586+37.00	Med.	32597					3638			
575+45.00 - 576+80.00	Rt.		135.0	1.3				20		
576+80.00 - 579+95.00	Rt.		315.0	1.3				47		
579+95.00 - 580+62.00	Rt.		67.0	1.3				10		
580+62.00 - 586+37.00	Med.		575.0	1.3				85		
580+62.00 - 586+37.00	Rt.		575.0	1.3				85		
<b>SB 1-00</b>										
570+00.00 - 580+62.00	Med.		1062.0	1.3				157		
570+00.00 - 586+37.00	Med.	32598					3638			
570+01.00 - 586+38.00	Lt.	32599					6184			
570+00.00 - 574+57.00	Lt.		457.0	1.3				68		
575+45.00 - 577+25.00	Lt.		180.0	1.3				27		
577+25.00 - 580+34.00	Lt.		309.0	1.3				46		
580+34.00 - 580+62.00	Lt.		28.0	1.3				4		
580+62.00 - 586+37.00	Med.		575.0	1.3				85		
580+62.00 - 586+37.00	Lt.		575.0	1.3				85		
<b>Ramp A</b>										
182+99.00 - 187+24.00	Lt.		425.0	1.3				63		
182+99.00 - 187+24.00	Lt.	32600					708			
180+87.00 - 187+74.00	Rt.		687.0	1.3				102		
180+87.00 - 187+74.00	Rt.	32601					229			
<b>Ramp B</b>										
276+62.00 - 281+75.00	Lt.		513.0	1.3				76		
276+62.00 - 281+75.00	Lt.	32602					969			
274+47.00 - 280+29.00	Rt.		582.0	1.3				86		
274+47.00 - 280+29.00	Rt.	32603					1293			
<b>Ramp C</b>										
382+45.00 - 386+88.00	Rt.		443.0	1.3				66		
382+45.00 - 386+88.00	Rt.	32604					1723			
381+95.00 - 388+30.00	Lt.		635.0	1.3				94		
381+95.00 - 388+30.00	Lt.	32605					1552			
<b>Ramp D</b>										
481+05.00 - 485+63.00	Lt.		458.0	1.3				68		
481+05.00 - 485+63.00	Lt.	32606					967			
480+64.00 - 487+31.00	Rt.		667.0	1.3				99		
480+64.00 - 487+31.00	Rt.	32607					2446			
<b>Drainage Structures</b>								807		
<b>Paved Ditches</b>								278		
<b>SUB-TOTAL:</b>					29531		2682			
<b>TOTAL:</b>					29531		2682			

**EXHIBIT SQ-1**  
Date: 1/1/14

<b>REVISIONS</b>				<b>STATE OF FLORIDA</b>			<b>SUMMARY OF QUANTITIES</b>	<b>SHEET NO.</b>
DATE	DESCRIPTION	DATE	DESCRIPTION	<b>DEPARTMENT OF TRANSPORTATION</b>				
				ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
				10	LEON	123456-1-52-01		

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23-.003, F.A.C.

**SUMMARY OF SIDE DRAIN & MITERED END SECTIONS**

LOCATION	SIDE	PIPE LENGTH					MES					DESIGN NOTES	CONSTRUCTION REMARKS
		LF					EA						
		15"	18"	24"	30"	36"	15"	18"	24"	30"	36"		
STA. TO STA.													
150+10 - 150+50	Rt.	40.0					2						
160+85 - 161+21	Lt.		36.0					2					
176+36 - 176+78	Lt.				42.0					2			
181+46 - 181+98	Rt.			52.0					2				
192+46 - 192+82	Lt.	36.0					2						
194+50 - 195+14	Rt.					64.0					2		
<b>SUB-TOTAL:</b>		76	36	52	42	64	4	2	2	2	2		
<b>TOTAL:</b>		76	36	52	42	64	4	2	2	2	2		

**SUMMARY OF DITCH PAVEMENT**

LOCATION	SIDE	AREA ID	RIPRAP (SAND CEMENT)		DITCH PAVEMENT		DESIGN NOTES	CONSTRUCTION REMARKS	
			0530	1	0524	1			1
			CY		SY				
STA. TO STA.			P	F	P	F			
128+17.00	Lt.	52700	21.60						
128+52.00	Rt.	52701	24.20						
137+12.00 (S-2)	Lt.	52703				26.0			
156+14.00 (S-6)	Lt.	52704				30.0			
158+00.00 (S-7)	Lt./Rt.	52705				96.0			
161+20.00 (S-9)	Lt.	52706				40.0			
168+40.00 (S-12)	Rt.	52707				108.0			
172+87.00 (S-15)	Rt.	52708				56.0			
180+12.00 (S-17)	Lt.	52709				20.0			
182+57.00 (S-20)	Rt.	52710				20.0			
<b>SUB-TOTAL:</b>			45.8		396				
<b>TOTAL:</b>			45.8		396				

EXHIBIT SQ-2  
Date: 1/1/14

<p align="center">REVISIONS</p> <table border="1"> <thead> <tr> <th>DATE</th> <th>DESCRIPTION</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>				DATE	DESCRIPTION	DATE	DESCRIPTION					STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION <table border="1"> <thead> <tr> <th>ROAD NO.</th> <th>COUNTY</th> <th>FINANCIAL PROJECT ID</th> </tr> </thead> <tbody> <tr> <td align="center">10</td> <td align="center">LEON</td> <td align="center">123456-1-52-01</td> </tr> </tbody> </table>	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	10	LEON	123456-1-52-01	SUMMARY OF QUANTITIES	SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION																	
ROAD NO.	COUNTY	FINANCIAL PROJECT ID																		
10	LEON	123456-1-52-01																		

FOR PROJECTS WITH CROSS SECTIONS

SUMMARY OF EARTHWORK					
PAY ITEM NO.	PAY ITEM DESCRIPTION	CY		DESIGN NOTES	CONSTRUCTION REMARKS
		P	F		
	ROADWAY EXCAVATION, MAINLINE	10000			
	ROADWAY EXCAVATION, ADAMS ST.	800			
	REGULAR EXCAVATION, POND #1	1005			
	REGULAR EXCAVATION FROM LATERAL DITCHES	5000			
0120-1	TOTAL REGULAR EXCAVATION	16805			
	EMBANKMENT, MAINLINE	20000			
	EMBANKMENT, ADAMS ST.	7000			
0120-6	TOTAL EMBANKMENT	27000			
	SUBSOIL EXCAVATION, MAINLINE	2080			
	SUBSOIL EXCAVATION, ADAMS ST.	1100			
0120-4	TOTAL SUBSOIL EXCAVATION	3180			

Earthwork has been calculated using the \_\_\_\_\_ base option.  
 If another option is constructed, there shall be no revision to the earthwork quantities for which payment is made by Plan Quantity.

FOR PROJECTS WITHOUT CROSS SECTIONS

Adjustment percentages shown are for example only.  
 Contact District Materials Office or Construction for actual percentages to be used for each project.

SUMMARY OF EARTHWORK					
PAY ITEM NO.	PAY ITEM DESCRIPTION	CY		DESIGN NOTES	CONSTRUCTION REMARKS
		P	F		
	FILL, MAINLINE	253			
	FILL, GUARDRAIL LOCATIONS	70			
	FILL, CROSS DRAINS	100			
	SUB-TOTAL FILL	423			
	FILL ADJUSTMENT (20%) (423 X 0.20)	+85			
	SUB-TOTAL WITH FILL ADJUSTMENT	508			
	TRUCK ADJUSTMENT (25%) (571 X 0.25)	+127			
0120-2-2	TOTAL BORROW EXCAVATION	635			

EXHIBIT SQ-3  
 Date: 1/1/14

REVISIONS				STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			SUMMARY OF QUANTITIES	SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION	ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
				10	LEON	422823-1-52-01		

SUSERS

SDATES

STINES

SFILE

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.003, F.A.C.

**SUMMARY OF PERMANENT CRASH CUSHIONS**

LOCATION	SIDE	BARRIER SYSTEM		DESIGN LENGTH	DESIGN SPEED	CRASH TEST LEVEL	HAZARD WIDTH	LENGTH RESTRICTION	CRASH CUSHION		DESIGN NOTES	CONSTRUCTION REMARKS
		CONCRETE BARRIER WALL	GUARDRAIL						0544	75		
STATION				FT	MPH	TL-2 / TL-3	IN	FT	P	F		
100+64.50	Lt./Rt.		SGL FACE	18.75	60	TL-3	15.25	N/A	2		STD. GUARDRAIL TRANS.	
103+77.00	Med.		DBL FACE	18.75	60	TL-3	24.50	N/A	1		STD. GUARDRAIL TRANS.	
110+45.00	Med.	FULL WALL		15.00	60	TL-3	24.00	23.75	1		BIDIRECTIONAL TRAFFIC	
125+25.00	Rt.	HALF WALL		15.00	70	TL-3	15.00	N/A	1		UNIDIRECTIONAL TRAFFIC	
775+19.25	Rt.	BRIDGE WALL		12.50	35	TL-2	15.00	15.50	1		DRIVE ENTRANCE RESTRICTON	
995+40.75	Rt.		SPECIAL	15.63	50	TL-3	69.00	39.25	1		GORE AREA (EXIT RAMP)	
SUB-TOTAL:									7			
TOTAL:									7			

**Notes:**

- The DESIGN LENGTH column identifies the Shortest Crash Cushion Option and the LENGTH RESTRICTION column identifies the Longest Crash Cushion Option. When a LENGTH RESTRICTION is not applicable (N/A), then the Contractor has the option to select valid Crash Cushions from the Qualified Products List (QPL) which have design lengths greater than or equal to the length identified in the DESIGN LENGTH column.
- For Additional Information on the Design Length of Permanent Crash Cushions, see Design Standards, Index 430.
- For Length Restrictions, refer to the Crash Cushion Drawings on the Qualified Product List (QPL).

**EXHIBIT SQ-4**  
Date: 1/1/14

REVISIONS					STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			SUMMARY OF QUANTITIES	SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION		ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
					10	LEON	123456-1-52-01		



**SUMMARY OF EROSION AND SEDIMENT CONTROL DEVICES**

LOCATION  STA. TO STA.	SIDE	AREA ID	ARTIFICIAL COVERINGS		SEDIMENT BASIN		SEDIMENT BASIN CLEANOUT		SEDIMENT BARRIER		FLOATING TURBIDITY BARRIER		STAKED TURBIDITY BARRIER		SOIL TRACKING PREVENTION DEVICE		INLET PROTECTION SYSTEM		DESIGN NOTES	CONSTRUCTION REMARKS
			0104 1		0104 7		0104 9		0104 10 3		0104 11		0104 12		0104 16		0104 18			
			SY		EA		EA		LF		LF		LF		EA		EA			
			P	F	P	F	P	F	P	F	P	F	P	F	P	F	P	F		
160+55 TO 165+16	Lt.								482.0											
159+94 TO 163+75	Rt.								381.0											
152+55	Lt.								30.0											
154+20	Lt.								25.0											
152+18	Rt.								30.0											
154+13	Rt.								26.0											
156+94 TO 158+38	Lt.								144.0											
158+38	Lt.								27.0											
157+23 TO 158+64	Rt.								141.0											
160+44	Rt.								28.0											
160+45	Lt.								27.0											
158+88 TO 160+25	Lt.									137.0										
158+64 TO 160+03	Rt.									138.0										
158+60 TO 159+20	Rt.											153.0								
159+67 TO 160+35	Lt.											133.0								
160+78	Lt.																	1		
160+78	Rt.																	1		
160+78	Rt.																	1		
160+80	Lt.	35567	22.0																	
SUB-TOTAL:			22						1341		275		286					3		
TOTAL:			22						1341		275		286					3		

**EXHIBIT SQ-6**  
Date: 1/1/14

REVISIONS				STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION					
ROAD NO. 10		COUNTY LEON	FINANCIAL PROJECT ID 123456-1-52-01					

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.003, F.A.C.

SUMMARY OF GUARDRAIL

LOCATION  STA. TO STA.	SIDE	GUARDRAIL				BRIDGE ANCHORAGE ASSEMBLY		END ANCHORAGE ASSEMBLY				PIPE RAIL		RUB RAIL		DESIGN NOTES	CONSTRUCTION REMARKS	
		536-1-1		536-1-3		536-8-1		536-85-22		536-85-25		536-6		536-5-1				
		LF		LF		EA		EA		EA		LF		LF				
		P	F	P	F	P	F	P	F	P	F	P	F	P	F			
600+50.00 - 601+37.00	Rt.	87.5				1		1										
600+10.00 - 601+35.00	Lt.	125.0				1		1										
602+25.00 - 603+25.00	Rt.	100.0						1		1								
602+30.00 - 603+00.00	Rt.											70						
600+50.00 - 603+25.00	Med.			275.0		1		1										
600+70.00 - 601+20.00	Med.												50					
604+25.00 - 604+87.00	Rt.	62.5						1										
602+45.00 - 603+20.00	Lt.	75.0								1								
SUB-TOTAL :		450		275		3		5		2		70		50				
PLAN TOTAL :		450		275		3		5		2		70		50				
FINAL TOTAL :																		

**EXHIBIT SQ-7**  
Date: 1/1/14

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.003, F.A.C.

REVISIONS			
DATE	DESCRIPTION	DATE	DESCRIPTION

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION		
ROAD NO.	COUNTY	FINANCIAL PROJECT ID
10	LEON	123456-1-52-01

**SUMMARY OF QUANTITIES**

SHEET NO.

