

**SUMMARY OF PERFORMANCE TURF**

LOCATION STA. TO STA.	SIDE	AREA ID	LENGTH	WIDTH	PERFORMANCE TURF		PERFORMANCE TURF (SOD)		DESIGN NOTES	CONSTRUCTION REMARKS	
					0570	1 1	0570	1 2			
					SY		SY				
						P	F	P	F		
<b>NB 1-00</b>											
570+00.00 - 580+62.00	Med.		1062.0	1.3				157			
570+00.00 - 574+57.00	Rt.		457.0	1.3				68			
570+00.00 - 586+37.00	Rt.	32596					6184				
570+00.00 - 586+37.00	Med.	32597					3638				
575+45.00 - 576+80.00	Rt.		135.0	1.3				20			
576+80.00 - 579+95.00	Rt.		315.0	1.3				47			
579+95.00 - 580+62.00	Rt.		67.0	1.3				10			
580+62.00 - 586+37.00	Med.		575.0	1.3				85			
580+62.00 - 586+37.00	Rt.		575.0	1.3				85			
<b>SB 1-00</b>											
570+00.00 - 580+62.00	Med.		1062.0	1.3				157			
570+00.00 - 586+37.00	Med.	32598					3638				
570+01.00 - 586+38.00	Lt.	32599					6184				
570+00.00 - 574+57.00	Lt.		457.0	1.3				68			
575+45.00 - 577+25.00	Lt.		180.0	1.3				27			
577+25.00 - 580+34.00	Lt.		309.0	1.3				46			
580+34.00 - 580+62.00	Lt.		28.0	1.3				4			
580+62.00 - 586+37.00	Med.		575.0	1.3				85			
580+62.00 - 586+37.00	Lt.		575.0	1.3				85			
<b>Ramp A</b>											
182+99.00 - 187+24.00	Lt.		425.0	1.3				63			
182+99.00 - 187+24.00	Lt.	32600					708				
180+87.00 - 187+74.00	Rt.		687.0	1.3				102			
180+87.00 - 187+74.00	Rt.	32601					229				
<b>Ramp B</b>											
276+62.00 - 281+75.00	Lt.		513.0	1.3				76			
276+62.00 - 281+75.00	Lt.	32602					969				
274+47.00 - 280+29.00	Rt.		582.0	1.3				86			
274+47.00 - 280+29.00	Rt.	32603					1293				
<b>Ramp C</b>											
382+45.00 - 386+88.00	Rt.		443.0	1.3				66			
382+45.00 - 386+88.00	Rt.	32604					1723				
381+95.00 - 388+30.00	Lt.		635.0	1.3				94			
381+95.00 - 388+30.00	Lt.	32605					1552				
<b>Ramp D</b>											
481+05.00 - 485+63.00	Lt.		458.0	1.3				68			
481+05.00 - 485+63.00	Lt.	32606					967				
480+64.00 - 487+31.00	Rt.		667.0	1.3				99			
480+64.00 - 487+31.00	Rt.	32607					2446				
<b>Drainage Structures</b>								807			
<b>Paved Ditches</b>								278			
<b>SUB-TOTAL:</b>					29531			2682			
<b>TOTAL:</b>					29531			2682			

**EXHIBIT SQ-1**  
Date: 1/1/14

REVISIONS DATE DESCRIPTION DATE DESCRIPTION				STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			<b>SUMMARY OF QUANTITIES</b>	SHEET NO.
ROAD NO.	COUNTY	FINANCIAL PROJECT ID		10	LEON	123456-1-52-01		
SUSERS SDATES STIMES SFILE								

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23-.003, F.A.C.

**SUMMARY OF SIDE DRAIN & MITERED END SECTIONS**

LOCATION STA. TO STA.	SIDE	PIPE LENGTH LF					MES EA					DESIGN NOTES	CONSTRUCTION REMARKS
		15"	18"	24"	30"	36"	15"	18"	24"	30"	36"		
150+10 - 150+50	Rt.	40.0					2						
160+85 - 161+21	Lt.		36.0					2					
176+36 - 176+78	Lt.				42.0					2			
181+46 - 181+98	Rt.			52.0					2				
192+46 - 192+82	Lt.	36.0					2						
194+50 - 195+14	Rt.					64.0					2		
<b>SUB-TOTAL:</b>		76	36	52	42	64	4	2	2	2	2		
<b>TOTAL:</b>		76	36	52	42	64	4	2	2	2	2		

**SUMMARY OF DITCH PAVEMENT**

LOCATION STA. TO STA.	SIDE	AREA ID	RIPRAP (SAND CEMENT)		DITCH PAVEMENT		DESIGN NOTES	CONSTRUCTION REMARKS
			0530	1	0524	1		
			CY		SY			
			P	F	P	F		
128+17.00	Lt.	52700	21.60					
128+52.00	Rt.	52701	24.20					
137+12.00 (S-2)	Lt.	52703			26.0			
156+14.00 (S-6)	Lt.	52704			30.0			
158+00.00 (S-7)	Lt./Rt.	52705			96.0			
161+20.00 (S-9)	Lt.	52706			40.0			
168+40.00 (S-12)	Rt.	52707			108.0			
172+87.00 (S-15)	Rt.	52708			56.0			
180+12.00 (S-17)	Lt.	52709			20.0			
182+57.00 (S-20)	Rt.	52710			20.0			
<b>SUB-TOTAL:</b>			45.8		396			
<b>TOTAL:</b>			45.8		396			

**EXHIBIT SQ-2**  
Date: 1/1/14

REVISIONS				STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			<b>SUMMARY OF QUANTITIES</b>	SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION	ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
				10	LEON	123456-1-52-01		

FOR PROJECTS WITH CROSS SECTIONS

SUMMARY OF EARTHWORK					
PAY ITEM NO.	PAY ITEM DESCRIPTION	CY		DESIGN NOTES	CONSTRUCTION REMARKS
		P	F		
	ROADWAY EXCAVATION, MAINLINE	10000			
	ROADWAY EXCAVATION, ADAMS ST.	800			
	REGULAR EXCAVATION, POND #1	1005			
	REGULAR EXCAVATION FROM LATERAL DITCHES	5000			
0120-1	TOTAL REGULAR EXCAVATION	16805			
	EMBANKMENT, MAINLINE	20000			
	EMBANKMENT, ADAMS ST.	7000			
0120-6	TOTAL EMBANKMENT	27000			
	SUBSOIL EXCAVATION, MAINLINE	2080			
	SUBSOIL EXCAVATION, ADAMS ST.	1100			
0120-4	TOTAL SUBSOIL EXCAVATION	3180			

Earthwork has been calculated using the \_\_\_\_\_ base option.  
 If another option is constructed, there shall be no revision to the earthwork quantities for which payment is made by Plan Quantity.

FOR PROJECTS WITHOUT CROSS SECTIONS

Adjustment percentages shown are for example only.  
 Contact District Materials Office or Construction for actual percentages to be used for each project.

SUMMARY OF EARTHWORK					
PAY ITEM NO.	PAY ITEM DESCRIPTION	CY		DESIGN NOTES	CONSTRUCTION REMARKS
		P	F		
	FILL, MAINLINE	253			
	FILL, GUARDRAIL LOCATIONS	70			
	FILL, CROSS DRAINS	100			
	SUB-TOTAL FILL	423			
	FILL ADJUSTMENT (20%) (423 X 0.20)	+85			
	SUB-TOTAL WITH FILL ADJUSTMENT	508			
	TRUCK ADJUSTMENT (25%) (571 X 0.25)	+127			
0120-2-2	TOTAL BORROW EXCAVATION	635			

EXHIBIT SQ-3  
 Date: 1/1/14

REVISIONS				STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			SUMMARY OF QUANTITIES	SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION	ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
				10	LEON	422823-1-52-01		

SUSERS SDATES STINES SFILE

**SUMMARY OF PERMANENT CRASH CUSHIONS**

LOCATION	SIDE	BARRIER SYSTEM		DESIGN LENGTH	DESIGN SPEED	CRASH TEST LEVEL	HAZARD WIDTH	LENGTH RESTRICTION	CRASH CUSHION		DESIGN NOTES	CONSTRUCTION REMARKS
		CONCRETE BARRIER WALL	GUARDRAIL						0544	75		
STATION				FT	MPH	TL-2 / TL-3	IN	FT	P	F		
100+64.50	Lt./Rt.		SGL FACE	18.75	60	TL-3	15.25	N/A	2		STD. GUARDRAIL TRANS.	
103+77.00	Med.		DBL FACE	18.75	60	TL-3	24.50	N/A	1		STD. GUARDRAIL TRANS.	
110+45.00	Med.	FULL WALL		15.00	60	TL-3	24.00	23.75	1		BIDIRECTIONAL TRAFFIC	
125+25.00	Rt.	HALF WALL		15.00	70	TL-3	15.00	N/A	1		UNIDIRECTIONAL TRAFFIC	
775+19.25	Rt.	BRIDGE WALL		12.50	35	TL-2	15.00	15.50	1		DRIVE ENTRANCE RESTRICTON	
995+40.75	Rt.		SPECIAL	15.63	50	TL-3	69.00	39.25	1		GORE AREA (EXIT RAMP)	
									SUB-TOTAL:	7		
									TOTAL:	7		

**Notes:**

- The DESIGN LENGTH column identifies the Shortest Crash Cushion Option and the LENGTH RESTRICTION column identifies the Longest Crash Cushion Option. When a LENGTH RESTRICTION is not applicable (N/A), then the Contractor has the option to select valid Crash Cushions from the Qualified Products List (QPL) which have design lengths greater than or equal to the length identified in the DESIGN LENGTH column.
- For Additional Information on the Design Length of Permanent Crash Cushions, see Design Standards, Index 430.
- For Length Restrictions, refer to the Crash Cushion Drawings on the Qualified Product List (QPL).

**EXHIBIT SQ-4**  
Date: 1/1/14

<table border="0"> <tr> <th colspan="2">REVISIONS</th> </tr> <tr> <td>DATE</td> <td>DESCRIPTION</td> </tr> <tr> <td> </td> <td> </td> </tr> </table>				REVISIONS		DATE	DESCRIPTION			STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION	ROAD NO. COUNTY FINANCIAL PROJECT ID 10 LEON 123456-1-52-01	<b>SUMMARY OF QUANTITIES</b>	SHEET NO. _____
REVISIONS													
DATE	DESCRIPTION												





**SUMMARY OF GUARDRAIL**

LOCATION	SIDE	GUARDRAIL				BRIDGE ANCHORAGE ASSEMBLY		END ANCHORAGE ASSEMBLY				PIPE RAIL		RUB RAIL		DESIGN NOTES	CONSTRUCTION REMARKS	
		536-1-1		536-1-3		536-8-1		536-85-22		536-85-25		536-6		536-5-1				
		LF		LF		EA		EA		EA		LF		LF				
STA. TO STA.		P	F	P	F	P	F	P	F	P	F	P	F	P	F			
600+50.00 - 601+37.00	Rt.	87.5				1		1										
600+10.00 - 601+35.00	Lt.	125.0				1		1										
602+25.00 - 603+25.00	Rt.	100.0						1		1								
602+30.00 - 603+00.00	Rt.											70						
600+50.00 - 603+25.00	Med.			275.0		1		1										
600+70.00 - 601+20.00	Med.												50					
604+25.00 - 604+87.00	Rt.	62.5						1										
602+45.00 - 603+20.00	Lt.	75.0								1								
SUB-TOTAL:		450		275		3		5		2		70		50				
PLAN TOTAL:		450		275		3		5		2		70		50				
FINAL TOTAL:																		

**EXHIBIT SQ-7**  
Date: 1/1/14

<b>REVISIONS</b>					STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			<b>SUMMARY OF QUANTITIES</b>	SHEET NO.
DATE	DESCRIPTION	DATE	DESCRIPTION		ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
					10	LEON	123456-1-52-01		

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.003, F.A.C.

