




Utilization of Intelligent Compaction (IC) for Acceptance

Civil Integrated Management (CIM)
June 15, 2012
Disney's Coronado Springs Resort


Rebecca Embacher, M.S., P.E.
Minnesota Department of Transportation



Your Destination...Our Priority

Outline

- IC Background
- Lessons Learned
 - Training / Education
 - Data Management
 - QC: Impacts on Contractor
 - Project Management
 - Certifications
 - VT: Data Mining Findings
- Where are we going?





Roller Measurement Values

Ammann
 k_b

Caterpillar
CMV, MDP

HAMM/Wirtgen
HMV

Bomag
 E_{VIB}

Dynapac
CMV

Sakai
CCV

Courtesy Transtec, Inc.

Icons: Bus, Train, Ship, Airplane, Car, Bicycle, Motorcycle, Scooter

Benefits Observed by Contractors

- **Real-time feedback to operators**
 - Increased Accountability
 - Coverage
 - Prevent Gaps between passes
 - Compaction Curves
 - ↓ Number of Passes
 - Identify Weak Areas
 - Moisture Control (Grading Applications)
 - View Temp (HMA applications)
- **GPS System Transferrable**

Icons: Bus, Train, Ship, Airplane, Car, Bicycle, Motorcycle, Scooter




Expected Benefits

- 100% Coverage
- Real-Time, Digital, Permanent Results
- Increased
 - Compaction Uniformity
 - Inspector Safety
 - Grade Control
 - Speed Control
 - Record Keeping
 - Planning/Staging
 - Pavement Life




Sampling Coverage

Traditional Compaction Testing Method



1 / 1,000,000

Compaction Testing and Coverage Mapping with AccuGrade



100 % Coverage

Courtesy of Trimble/Caterpillar





Expected Benefits (Cont.)

- Decreased
 - Spot Testing (QC / VT)
 - Maintenance Costs / Preservation Activities
 - Inspection Time
- Link
 - In-situ Properties → Design & Performance



Training / Education

LESSONS LEARNED





Required Project Specific Training

(Certification of Quality Control Personnel)


- **Department**
 - Project Engineer
 - Inspector(s)
- **Contractor**
 - Field Grading/Paving Superintendent
 - QC Field Representative
 - IC Roller Operator(s)

















Required Project Specific Training

Presented By	Topic
IC Representative (Note 1)	<ul style="list-style-type: none"> • General Background Information. • Details on system relevant to both the Contractor and the Department. At a minimum: <ul style="list-style-type: none"> ▪ Data transfer <ul style="list-style-type: none"> ○ Manual ○ Web-Based Storage (Cloud Technology) ▪ Data Backup ▪ Recommended Operating Settings ▪ Data storage capacity of on-board documentation system ▪ Base station and repeater use, or use of VRS / CORS GPS system
Grading and Base / Bituminous Engineer	<ul style="list-style-type: none"> • Special Provisions • Goals • Forms



Field Training with IC Manufacturer

- Completed outside of project specific training
- 'Hands on' operation of the IC system
 - On-Board Documentation System
 - Proprietary Software
 - Modem / Radio Setup use)
 - Recommended Operating Settings



Contractor Field Training (cont.)

- Base Station / Repeater
 - Use / Placement
 - Calibration Files
 - Compatibility
- Technical Support Available
 - Duration of Project





Data Management

LESSONS LEARNED



Data Volume – Massive Amounts!



SP1380-63 (THS) 2011

15
Miles



3
Compactors


11,207
Export Files

17,271,460
Rows
(Raw Data)

7,750,844
Rows
(Valid Data)
















Data Review

- **Proof Data (final coverage)**
 - Final Pass Count
 - Final Stiffness
 - Final Temperature
- **All Passes (entire data set / pass)**
 - **Compaction Curve**
 - (Stiffness vs. Pass Count)
 - **Temperature Curve**
 - (Temperature vs. Pass Count)
 - **Spatial Analyses**
 - (Temperature, Pass Count, Stiffness)









Wireless Technology Needed!

(Now Available with Some Vendors)

- ↑ 'Near' Real-Time Review
- ↓ Handling Efforts
- ↓ Lost Data
 - Overwriting on Compactor
 - Human Error during Manual Transfer
 - Theft
- ↓ or Eliminate Duplicate Data





S-xx.2C Web-Based Storage


- **Wi-Fi Capabilities**
 - Modem or
 - Radio
- **Transfer data directly to web-base storage (Cloud Technology)**
- **USB Port (Manual Transfer)**




S-xx.2 Equipment Requirements

- **Provide Department**
 - Proprietary IC Software
 - Access to Web-Based Storage
- **Duration**
 - Prior to roller Certification
 - Until 6 months after final Grading Work (or final bituminous paving)








Intelligent Construction Data Management Tool












- Spatial Analysis
- Users:
 - Agency
 - Inspectors
 - Project Engineer
 - Contractor
 - Field Superintendent
 - QC Field Representative(s)
 - Specialty Units
 - Specification Refinement














View, Edit, Analyze













Statistic	Value
Min	5.50
Mean	19.37
Max	43.60
Standard Deviation	6.41
Coefficient of Variation	0.33
Sample Size	50,993






Staffing

- ↑ Job Duties
- ↑ Skills
 - Computer Literacy
 - Organization Skills
 - Detailed
 - Communication / Leadership
- ↑ Resources
 - Temporary Hires
 - Switching Workers Around



Increased Coordination / Time

- Training
- Computer Equipment
- Roller Placement
- Data Transfer (for non-wireless transfer)

Compactor Operator

➡

QC Field Representative









➡

Contractor Project Manager

➡

Agency

- Time already maxed!
- Daily Base Station / Repeaters Preparation



S-xx.2C Web-Based Storage

- **Wi-Fi Capabilities**
 - Modem, or
 - Radio
- **Transfer Data directly to web-base storage (Cloud Technology)**
- **USB Port**



S-xx.2C GPS Network

- **System to Connect to:**
 - Virtual Reference Station / Continuously Operating Reference Station (VRS / CORS)
- **Poor Cellular Coverage**
 - Real Time Kinematic – Global Positioning System (RTK-GPS)





Staging

- IC Equipment – Needed Multi-places at same time
- Haul Roads
 - Blocked by Measurement Pass Area
 - (Surface Prep. Important)
- Break Down of Compactor or IC System?



Satellite/Cellular Connectivity

Base Station Server Down?
Limited Cellular Data Coverage?

- Would further work be unauthorized?
- Affects on Incentives/Dis-incentives?
- QC / VT rates adjustments?





Quality Control (QC)

Impacts on Contractor and Agency - Certifications

LESSONS LEARNED




National Needs


- No Standardized Output
- No Independent Calibration Centers
(e.g., FWD National Calibration Centers, Profilographs)




<h1 style="margin: 0;">Roller Certification</h1>							
INTELLIGENT COMPACTION METHOD ROLLER CERTIFICATION FORM Grading & Base Manual 5-692.XXX				G&B-702 (06/04/12) PROJECT NO.: _____			
CONTINUOUS COMPACTION CONTROL SYSTEM			ROLLER INFORMATION				
Manufacturer Name: _____ Retrofit System (Yes/No): _____ Automatic Feedback Control (Yes / No) _____ Name of MV and Unit (e.g., CMV, unitless) _____ MV Sensor Range (e.g., 0 to 150) _____			Machine Model: _____ Machine Type: _____ Drum Width: _____ Drum Diameter: _____ Machine Weight: _____				
ON-BOARD DISPLAY			VERIFICATION OF SYSTEM				
Displays MV Output (Yes/No) _____ Displays Alignment (Yes/No) _____			Observed Avg MV over 'Soft' Material (Case 1) _____ Observed Avg MV over 'Stiff' Material (Case 2) _____ Measurements continuously recorded over Case 3 area (Yes/No) _____ GPS appears to be recording correctly (Yes/No) _____ MVs reflect sensor range (Yes/No) _____ System appears to be reporting/recording correctly (Yes/No) _____				
OPERATING SETTINGS REQ'D DURING FINAL MEASUREMENT PASS			<input type="checkbox"/> All certification data transferred to web-based storage. <input type="checkbox"/> All certification data manually transferred.				
			Contractor Signature: I certify that the listed compactor complies with the CCC requirements:				
			Agency / Owner Signature: This Certification was Reviewed and Accepted by:				
VERIFICATION OF GPS ACCURACY							
Position	Compactor		Independent Device (e.g., Rover)		Accuracy		Pass / Fail
	X-Coordinate (A)	Y-Coordinate (B)	X-Coordinate (C)	Y-Coordinate (D)	ΔX abs [(A) - (C)]	ΔY abs [(B) - (D)]	
1							
2							
3							
4							
5							
6							
Is Offset Present between GPS antenna and center of drum (Yes/No)?							
If "Yes", has necessary offset been inputted and validated (Yes/No)?							
cc: Grading and Base Engineer							









<h1 style="margin: 0;">S-xx.3B Certification of IC Roller</h1>				
TABLE S-xx.3				
INSTRUMENTED ROLLER CERTIFICATION				
Case No.	Demonstration	No. of Measurement Passes	Measurement Area	
			Width	Length
VERIFICATION OF ADEQUATE SENSOR RANGE				
1	Soft Material: MVs	1	≥ 14 ft (4 m)	≥ 300 ft (100 m)
2	Stiff Material: MVs			
VERIFICATION OF DATA CONTAINED WITHIN MEASUREMENT PASS FILES				
3	Requirements of S-xx.2	2	Layer	≥ 300 ft (100 m)



 **S-xx.3B4 Verification of IC GPS Accuracy**

- Establish and mark a spot, on ground level
 - Prevent climbing onto compactor drum
- Collect and compare GPS coordinates
 - Instrumented Compactor
 - Independent Measuring Device
 - Calibrated using control point
- Acceptable ΔX & $\Delta Y \leq 0.5$ ft



Icons at the bottom:        



Verification Testing (VT) – Data Mining Findings

LESSONS LEARNED




Verification Testing - Targets

One cannot easily implement a target stiffness value or coverage (pass count) as part of acceptance criteria.

COMPLEX

(IT HAS NEVER BEEN ACHIEVED IN MN)





Control Strip Areas

- Time Consuming / Costly
- Does it cut off the haul road?
- Large Number Constructed
 - Material Types (Proctors)
 - Moisture Content ($\sim \pm 2\%$)
- Difficulty Representing Fill
- Increased Inspection
- How to use Resulting CMV?












Photo Courtesy of Mathiowetz Construction





















S-xx.3C Measurement Passes

- **Previously Required:**
 - **Passing:**
 - 90% of the measurements $\geq 90\% \times \text{IC-Target Value}$ prior to placing next lift
 - **Corrective Action:**
 - Areas $< 80\% \times \text{IC-Target Value}$
- **Currently not Requiring Control Strips**




S-xx.3C Measurement Passes

- **Previously Required:**
 - Bottom of Fill / Cut up to grading grade.
 - **Measurement Pass Layers:**
 - ~ 2 ft.
- **Currently Require Measurement Passes:**

Table S-xx.4	
Required Measurement Pass Locations	
Specification	Measurement Pass Location
2105 / 2106(SP)	Top of Subgrade
	When the depth is within 6 ft (2 m) below of Grading Grade.
	Grading Grade
2211	Top of the Base
2215	Top of the Reclaimed Base
2331	





Promote Certifications & IC Use

(A) Instrumented Roller Certification.....5% Payment

(B) QC Field Rep. Certification.....5% Payment

(C) IC Roller Operator(s) Certification..... 10% Payment

(D) 10% Measurement Pass Completion.....8% Payment

(E) 40% Measurement Pass Completion 24% Payment

(F) 70% Measurement Pass Completion 24% Payment


(G) 100% Measurement Pass Completion24% Payment


No payments for (D) – (G) until items (A) – (C) is approved.

No payment for (E) – (G), until item (D) is approved.


Payment for (D) – (G) will be made after Department review of data.

The Department will review the data within 10 business days after notification.





WHERE ARE WE GOING?





We can see the potential benefits.

Continue to pilot the technology.



2012 Construction Season


- **Stabilized Full Depth Reclamation**

- 1 Pad Foot
- 1 Pneumatic
- 1 Double-Drum, Rubber-Steel
- 1 Double-Drum Steel

- **HMA Project (Entire Rolling Train)**

- 2 Pneumatic
- 2 Double-Drum Steel





**Thank you
for your attention, time and
support!**

Your Destination...Our Priority

