



Bid Questions and Answers Report

Date & Time: 1/25/2017 8:49:04 AM

District Address: District 7 Construction Office, located at 11201 N McKinley, Tampa, FL 33612

District Phone: (813) 975-6285

Proposal: T7389

Project: 432720-1-52-01

Letting Date: 1/25/2017

Location: CENTRAL OFFICE

Description: SR 55 (US 19)

Question:	16930: On Sheet 32 of the WM/FM Utility Plans there is a call out for a 3" Gate Valve on the 4" line. There is no symbol showing it's location. Please clarify placement and size.	Posted:	1/6/2017 11:35:45 AM
Answer:	The callout for 3" Gate Valve has been removed, see Revision 1 sheet U-32.	Status:	ANSWER PUBLISHED
		Posted:	1/13/2017 2:30:55 PM
Question:	16931: On Sheet 32 of the WM/FM utility plans there is a call out for a 20" - 90 Bend & 20" -45 Bend on the 12" WM Deflection. Please confirm these should be 12".	Posted:	1/6/2017 11:37:14 AM
Answer:	The callouts are to be 12". Callout have been modified to be as follows: 12" - 90° Bend & 12" - 45° Bend, see Revision 1 sheet U-32.	Status:	ANSWER PUBLISHED
		Posted:	1/13/2017 2:30:02 PM
Question:	16932: On Sheet 32 of the WM/FM Utility plans the relocation of the 3" FM does not depict any line stops for deflecting this line. Please clarify if County can isolate this location with existing valves for this work or if a pay item for a line stop will be added.	Posted:	1/6/2017 11:40:24 AM
Answer:	The 3" FM can be isolated at the Private Lift Station. Line stop is not necessary.	Status:	ANSWER PUBLISHED
		Posted:	1/13/2017 2:28:51 PM
Question:	16934: On Sheets 28-29 it appears the tapping sleeves have also been accounted for as 20" Tees. Please clarify the 20" Tee quantity.	Posted:	1/6/2017 2:29:20 PM

Answer:	The Quantity for Item No. 1055 11425 (Utility Fittings, F&I, DI/CI Tee, 20 -49.9") has been removed from the Plans, please see Revision 1 sheet U-3.	Status:	ANSWER PUBLISHED
		Posted:	1/13/2017 2:27:38 PM
Question:	16935: Please clarify the 20 Utility fixtures that are to be removed, stockpiled and salvaged. None are shown on the plan.	Posted:	1/6/2017 2:47:33 PM
Answer:	This bid item has been removed, see Revision 1 sheet U-3. No existing fixtures are to be salvaged to the Owner. Removal and disposal of existing fixtures is to be included under pay item 1050 16002, pay item 1050 16004 and pay item 1050 16005.	Status:	ANSWER PUBLISHED
		Posted:	1/13/2017 4:41:28 PM
Answer:	This bid item has been removed, see Revision 1 sheet U-3. No existing fixtures are to be salvaged to the Owner. Removal and disposal of existing fixtures is to be included under pay item 10504.2 Existing Pipe Modify/Removal.	Status:	ANSWER VOIDED
		Posted:	1/13/2017 2:25:55 PM
Question:	17023: 1. Please publish schedule and calculations to support 350 calendar day time.	Posted:	1/16/2017 11:00:31 AM
Answer:	The request for this document is considered a public records request, therefore the requested information will be emailed by the department directly to you, as the requestor. The FDOTTracker number for this request is 17-00658. This information was emailed to the requestor on 1/20/2017.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 9:51:00 AM
Question:	17025: There are broad expanses of the existing grassed areas within the project limits that are not included in the plan quantity for performance turf. How is the following to be paid for: On the order of 38,000-sy existing turf outside FDOT construction limits are disturbed by HCUD work. Much of this turf is currently substandard as performance turf. How will this restoration be paid for?	Posted:	1/16/2017 11:05:21 AM
Answer:	The costs of sod outside FDOT construction limits, disturbed by Hernando County Utility work is included in the costs for the utility pipe (pay items 1050-11-222, 1050-11-224, 1050-11-225).Please refer to the TSP which states ¶ The unit price shall be full compensation for all materials, equipment and labor, including but not limited¶ .'.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 10:00:59 AM

Question:	17027: There is another 20,000-sy+ of existing substandard turf that is outside BOTH the FDOT and the HCUD construction limits. i. Is THIS classification of existing turf to be upgraded? ii. If so, how is this to be paid for?	Posted:	1/16/2017 11:06:51 AM
Answer:	20,000 -sy+ of existing substandard turf that are outside the limits of FDOT and HCUD construction limits are not require to be replaced.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 3:09:11 PM
Question:	17028: If ALL turf is to meet performance turf standards at the end of the job, the pay quantity appears to be on the order of 100,000-sy short of the actual total if median turf is included. Is Plan quantity of performance turf accurate?	Posted:	1/16/2017 11:09:01 AM
Answer:	The construction documents specify the areas that require sod, typical section sheets 4 and 5 do not show the median being sodded.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 9:57:09 AM
Question:	17048: Is there an intent to delete rumble striping (Item 546-72-53) from this project?	Posted:	1/17/2017 8:55:02 AM
Answer:	Rumble striping (pay item 546-72-53) has been approved for use on this project, see plan sheets S-1 through S-40 for locations.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 9:55:00 AM
Question:	17138: At the intersection of US19 at Lake in the Woods Dr and US19 at Northcliffe Blvd, the signalization plans call for the contractor to install new internally illuminated street signs on the existing poles. Can the contractor reuse the existing cantilever arms that are currently holding the existing street name signs or will the contractor be required to provide new cantilever arms?	Posted:	1/18/2017 3:39:03 PM
Answer:	The contractor will be required to provide new cantilever arms for the proposed internally illuminated street name signs. See sheets T-56 through T-58 for arm details.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 2:39:36 PM
Question:	17139: Pay item 0000700 5 Remove and Replace Existing Valve and Valve Box 2 EA. These valves do not appear in the callouts on the utility plans. Please identify the locations of the valves, type of valves, size of valves, and if they can be installed while the line is dead or do we need to use a line stop.	Posted:	1/18/2017 3:57:06 PM

Answer:	Please refer to Standard Specification Section "2-3 Interpretation of Estimated Quantities, 2-3.2 Contracts other than Lump Sum". The quantities for the above items shall be per the contract plans.	Status:	ANSWER PUBLISHED
		Posted:	1/20/2017 10:46:16 AM