



Bid Questions and Answers Report

Date & Time: 10/25/2017 8:34:29 AM

District Address: District 5 Construction Office, located at 719 South Woodland Blvd, Deland, FL 32720

District Phone: (386) 943-5350

Proposal: T5598

Project: 435661-1-52-01

Letting Date: 10/25/2017

Location: CENTRAL OFFICE

Description: SR 436

Question:	19681: On Plan Sheet No. 5 Summary of Side Streets the table provides the milling & resurfacing limit in feet. On the typical side street milling and resurfacing limits illustration it shows the length down c/l of side street from the edge of travel lane. Is this length from the edge of the travel lane or the edge of the bike lane? In addition, what is the milling & resurfacing limit for the driveway at Station 36+58 LT side?	Posted:	9/29/2017 11:30:04 AM
Answer:	The length is from the edge of travel lane which lines up with the lip of gutter. The length down any driveway or sidestreet not listed on Sheet No. 5 is zero feet.	Status:	ANSWER PUBLISHED
		Posted:	10/2/2017 8:37:50 AM
Question:	19869: Who is responsible for installing and removing the temporary bus stop signs? Lynx or Contractor?	Posted:	10/18/2017 2:01:53 PM
Answer:	Lynx is responsible for installing, removing or moving bus stop signs.	Status:	ANSWER PUBLISHED
		Posted:	10/20/2017 10:25:26 AM
Question:	19870: Who is responsible for relocation of bus stop furniture and/or shelters? Contractor or Lynx/Seminole County?	Posted:	10/18/2017 2:04:52 PM
Answer:	The Contractor will be responsible for relocating bus stop furniture per 7-11 Preservation of Existing Property.	Status:	ANSWER PUBLISHED
		Posted:	10/20/2017 10:26:14 AM

Question:	19871: The lane configuration is being modified to accommodate a 7' buffered bike lane. Please clarify if Contractor is to mill and resurface following the existing longitudinal joints (12+12+16) since the Plans do not indicate a slope break (if any). If Contractor is to place longitudinal joints in a new location, please specify since location of slope breaks are unknown.	Posted:	10/18/2017 4:51:15 PM
Answer:	The Contractor is to mill and resurface following the existing slopes. The existing slope breaks are to remain.	Status:	ANSWER PUBLISHED
		Posted:	10/20/2017 2:35:34 PM