

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	CT171025	Call Order: 012	Proposal: T5620	District:05
Counties:	LAKE			
Road Name:	CITY OF TAVARES			
Limits:	TAV-LEE TRAIL EXTENSION			
Project(s):	43367315201(*)	Federal Aid No:	D517012B	
Total Roadway Length:	0.260 Miles	Contract Days:	240	
Total Bridge Length:	0.000 Miles	Letting Date:	10/25/17	
Total Proposal Length:	0.260 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	
Proposal Budget Estimate:		\$925,597.00		

Please read the full advertisement

Description:

Prequalification per Rule 14-22 is not required.

A Builder's License or General Contractor's License is required for this project.

For buildings three (3) stories or less in height, a Builder's License or General Contractor's License is acceptable. Buildings more than 3 stories in height require a General Contractor's License. This building is less than 3 stories in height.

A copy of the license must be received prior to Award.

The improvements under this contract consist of the construction of a multi-use concrete and asphalt trail extension and adjacent restroom facility from Wooten Park to north of Sinclair Ave. and Ruby St.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 012 Proposal: T5620**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43367315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43367315201)	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,831.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0110- 1- 1	CLEARING & GRUBBING (43367315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	681.000
	0120- 6-	EMBANKMENT	CY	112.000
	0160- 4-	TYPE B STABILIZATION	SY	2,282.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,376.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	28.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	145.900
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	29.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	367.000
	0527- 2-	DETECTABLE WARNINGS	SF	22.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,111.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
<b>Section 0003 Landscape / Peripheral</b>				
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43367315201)	LS	1.000
	0590- 70-	IRRIGATION SYSTEM (43367315201)	LS	1.000
	0751- 36- 13	BICYCLE RACK, FURNISH & INSTALL, 7-10 BICYCLES	EA	2.000
	0751- 38- 14	BENCH, F&I, STEEL	EA	2.000
<b>Section 0004 Utilities</b>				
	1050- 31-203	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 3"	LF	100.000
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	11.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	20.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	261.000
	1055- 11-224	UTILITY FITTING, F&I, PVC, TEE, 8.0-19.9"	EA	1.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	1.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	2.000
	1644-113- 05	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1PUMPER, 2"	EA	1.000
<b>Section 0005 Architectural</b>				
	0750- 1- 19	ARCHITECTURAL, BUILDING, NEW, OTHER BUILDING (43367315201)	LS	1.000