

SUMMARY OF LUMP SUM ITEMS					
PAY ITEM NO.	PAY ITEM DESCRIPTION	QUANTITY		DESIGN NOTES	CONSTRUCTION REMARKS
		P	F		
0101 J	MOBILIZATION	1			

- PAY ITEM NOTES**
- 110- 1- 1 COST OF THE REMOVAL OF EXISTING MSE WALL AND CONCRETE RETAINING WALL TO BE INCLUDED IN THE COST OF CLEARING AND GRUBBING.
- 110- 86 ALL SALVAGEABLE MATERIAL DESIGNATED TO BE DELIVERED BY THE CONTRACTOR SHALL BE DELIVERED TO:  
5301 NE 39TH AVE.  
GAINESVILLE, FL 32609  
CONTACT GAINESVILLE OPERATIONS PROGRAM ENGINEER: (352) 381-4316
- 520- 1 COST OF ASPHALT BASE CURB PAD AND ADDITIONAL CURB THICKNESS REQUIRED TO BE INCLUDED IN THE COST OF CURB AND GUTTER.
- 536- 73 EXISTING GUARDRAIL IS TO BE DISMANTLED AND STOCKPILED WITHIN THE RIGHT OF WAY IN AREAS DESIGNATED BY THE ENGINEER FOR REMOVAL BY FDOT MAINTENANCE FORCES.
- 538- 1 THIS IS TO INCLUDE REPLACEMENT OF 10 PANELS, 1390 REGULAR POSTS AND 1 SPECIAL POST WHICH HAVE BEEN DETERMINED TO BE NON SALVAGEABLE. ADDITIONAL POSTS AND PANELS DETERMINED TO BE NON SALVAGEABLE DURING RESETTling SHALL BE PAID FOR UNDER 538-5 OF THE SPECIFICATIONS.
- 570- 1 - 1 INCLUDES APPROXIMATELY 94 SY TURF FOR TEMPORARY EROSION CONTROL.
- 570- 1 - 2 INCLUDES APPROXIMATELY 357 SY SOD FOR TEMPORARY EROSION CONTROL.
- ADDITIONAL PAY ITEM NOTES MAY BE CONTAINED WITH THE OTHER COMPONENTS OF THE CONTRACT PLANS SET.

SUMMARY OF MONITOR EXISTING STRUCTURES										
SITE NO.	LOCATION	STRUCTURE USAGE	INSPECTION & SETTLEMENT MONITORING		VIBRATION MONITORING		GROUNDWATER MONITORING		DESIGN NOTES	CONSTRUCTION REMARKS
			0108 1	0108 2	0108 3	0108 3				
	LS		LS		LS					
	P		F	P	F	P	F			
1	230 WALNUT ST	MUSEUM					X		CULVERT EXTENSION	
2	744 PINE CIRCLE	HISTORIC CEMETERY WALL	X						SHEET PILE INSTALLATION	
3	624 OAK DRIVE	ANTIQUE SHOP			X				MILLING AND RESURFACING	
4	888 OAK DRIVE	LASIK EYE SURGERY			X				PILE DRIVING OPERATIONS	
5	648 OAK DRIVE	BED & BREAKFAST	X		X				MILLING AND RESURFACING	
TOTAL:			1		1		1			

- INDEX OF SUMMARY OF QUANTITIES**
- SHEET NO. SHEET DESCRIPTION
- S0-1 SUMMARY OF LUMP SUM ITEMS, SUMMARY OF MONITOR EXISTING STRUCTURES, SUMMARY OF LITTER REMOVAL AND MOWING
- S0-2 - S0-6 SUMMARY OF TEMPORARY TRAFFIC CONTROL PLAN ITEMS
- S0-7 SUMMARY OF TEMPORARY SIGNALIZATION & DETECTION
- S0-8 - S0-13 SUMMARY OF EROSION AND SEDIMENT CONTROL DEVICES
- S0-14 - S0-19 SUMMARY OF LITTER REMOVAL AND MOWING
- S0-20 SUMMARY OF REMOVAL ITEMS
- S0-21 SUMMARY OF EARTHWORK
- S0-22 SUMMARY OF GEOTECHNICAL ITEMS
- S0-23 - S0-35 SUMMARY OF PAVEMENT
- S0-36 SUMMARY OF MISCELLANEOUS ASPHALT PAVEMENT
- S0-37 - S0-38 SUMMARY OF STRUCTURE QUANTITIES
- S0-39 SUMMARY OF UTILITY ADJUSTMENTS
- S0-40 SUMMARY OF MISCELLANEOUS DRAINAGE ITEMS
- S0-41 SUMMARY OF PERMANENT BARRIER WALL
- S0-42 SUMMARY OF CURB & GUTTER AND/OR TRAFFIC SEPARATORS
- S0-43 SUMMARY OF SIDEWALK & DETECTABLE WARNINGS
- S0-44 SUMMARY OF DITCH PAVEMENT
- S0-45 - S0-49 SUMMARY OF GUARDRAIL
- S0-50 SUMMARY OF PERMANENT CRASH CUSHIONS
- S0-51 - S0-53 SUMMARY OF PERFORMANCE TURF

AN INDEX IS OPTIONAL

THIS LIST INCLUDES EXISTING STRUCTURES (AS DETERMINED BY THE DEPARTMENT) LOCATED OUTSIDE THE LIMITS SPECIFIED IN ARTICLE 108-2 OF THE FOOT SPECIFICATIONS THAT ARE REQUIRED TO BE MONITORED. THIS LIST SHOULD NOT BE CONSIDERED ALL INCLUSIVE AND DOES NOT CONTAIN EXISTING STRUCTURES TO BE MONITORED THAT ARE LOCATED WITHIN THE DISTANCES SPECIFIED IN ARTICLE 108-2.

SUMMARY OF LITTER REMOVAL AND MOWING																	
CONST. PHASE	LOCATION	SIDE	DURATION (DAYS)	FREQUENCY (DAYS)	AREA ID	LITTER REMOVAL				MOWING				DESIGN NOTES	CONSTRUCTION REMARKS		
						0107 1				0107 2							
						AREA		AREA		AREA		AREA					
						CYCLES	TOTAL (AC)	CYCLES	TOTAL (AC)	CYCLES	TOTAL (AC)	CYCLES	TOTAL (AC)				
	STA. TO STA.																
1	159+44 TO 305+20	Lt.	42	30	35005	1	8.700	8.700		35005	1	8.700	8.700				
2	159+44 TO 305+20	Lt.	98	30	35120	3	7.300	21.900		35120	3	7.300	21.900				
3	159+44 TO 305+20	Rt.	114	30	35301	4	5.800	23.200		35301	4	5.800	23.200				
4	159+44 TO 305+20	Rt.	68	30	35301	2	5.800	11.600		35301	2	5.800	11.600				
SUB-TOTAL:								65.400		SUB-TOTAL:							65.400
TOTAL:								65.40		TOTAL:							65.40

EXHIBIT SQ-1  
Date: 1/1/16

REVISIONS				STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			SUMMARY OF QUANTITIES	SHEET NO. SQ-1
DATE	DESCRIPTION	DATE	DESCRIPTION	ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
				SR 10	LEON	123456-1-52-01		

THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE DIGITALLY SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.