Florida Department of Transportation
1000 NW 111 Avenue
Miami, FL 33172-5800

RON DESANTIS
GOVERNOR

KEVIN J. THIBAULT, P.E.
SECRETARY

# ADDENDUM NO. 1

DATE: June 18, 2020

TO: PROPOSERS

FROM: Suzanne Diaz
Procurement Office
District Six

RE: **Project/ Proposal No.: E-6M92**
Financial Project No.: 444444-2-52-01
County(ies): Miami-Dade County
Project Name: Low Bid Design Build Contract for SR-90/US HWY-41/TAMIAMI TRAIL FROM STRUCTURE S-333 TO STRUCTURE S-334.

---

Proposers and other interested parties are informed that the above referenced Project documents are hereby revised, changed and supplemented as set forth below.

The Request for Proposal (RFP) dated April 28, 2020, has been updated and provided with this Addendum No.: 1, along with the Reference Documents and Attachments. A compare file has been included.

| Page No(s). | Rev. Date | Description |
|---|---|---|
| RFP pg. II | 06/10/20 | ~~SFWMD R/W Occupancy Permit~~ |
| RFP pg. 2 | 06/10/20 | The Phase 2 Recommended Plan from the July 2018 and October 2019 VA proposed implementation of more modest conveyance improvements to enhance water flow by providing ~~eight~~ seven drainage culverts and six bridges in lieu of the previously approved 2.8 miles of Phase 2 bridging. |
| RFP pg. 2 | 06/10/20 | The project includes realigning and raising the profile of the existing roadway approximately two feet, placement of geotextiles for roadway and base reinforcement, utility coordination, construction of ~~8~~ 7 drainage culverts, 6 bridges, construction of drainage swales and harmonizing the proposed roadway to adjacent properties and canals within the project limits. |
| RFP pg. 9 | 06/10/20 | The Design-Build Firm's submitted Bid (~~time and~~ cost) is to be a lump sum Bid for completing the scope of work detailed in the Request for Proposal. |
| RFP pg. 31 | 06/10/20 | 2 set of 11 "X 17" copy of the signed and sealed As-Built plans, drawings and Certified Surveys (including as-built channel survey at all bridges, cross drains, and swale control structures) and to include plotted as-built cross section elements and elevations at all cross section stations in Concept Plans. |

| | | |
|---|---|---|
| RFP pg. 47 | 06/10/20 | At all culvert locations the existing A-8 material shall be removed down to the top of the limerock layer. The A-8 material removal shall transition on a 1:10 slope to connect to the existing as detailed in the concept plans sheet 82. Existing excavated material may be mixed with large boulders. Backfill and A-3 material shall be included in Lump Sum Bid. |
| RFP pg. 47 | 06/10/20 | The SHW elevation to be utilized for swale design shall be ~~8.75~~ 8.70 NGVD |
| RFP pg. 48 | 06/10/20 | Driveway connections shall be designed such that no drainage run-off shall discharge onto private property. Temporary parking shall be provided to all existing locations where parking is present. Contractor shall coordinate with the concessionaires/tribes. |
| RFP pg. 51 | 06/10/20 | Only Developmental Index number D20450 ~~and D20453 have~~ has been approved for use on this project. |
| RFP pg. 51 | 06/10/20 | The bridges may be designed to accommodate 2- 6" FPL conduits with conductors ~~(north side) and~~, 2-4" AT&T conduits with communication cable ~~(south side)~~, 2-6" Crown Castle conduits with fiber optics and associated hanger systems. Utilities shall not encroach into the minimal vertical clearance. See typical sections and Utility Work Schedules for additional information." |
| RFP pg. 55 | 06/10/20 | • Miccosukee Arts and Crafts Festival<br>• Native American Day<br>• Airboat Association of Florida - BBQ<br>• Airboat Association of Florida - Fish Fry |
| RFP pg. 60 | 06/10/20 | "Existing flashing beacon at approximate station 3746+20 shall be adjusted/relocated. Contractor shall coordinate with FDOT District 6 Traffic Operations and Miami-Dade County Public Works and Traffic." added to the end of the third paragraph. |
| RFP Attachment D | 06/10/20 | Updated "444444-2-52-01 Attachment D Technical Special Provision" |
| RFP Attachment E | 06/10/20 | Updated "444444-2-52-01 Attachment E Precast Concrete Construction - Florida Slab Beam Superstructure System" |
| RFP Attachment J | 06/10/20 | "444444-2-52-01 Attachment J Modified Special Provision" added |
| RFP, Reference Document 1.2 | 06/10/20 | Concept Plans Pg. 16 - Remove "***"<br>Concept Plans Pg. 32 - Replace "Lincoln Financial Tower" with "Pond 3A Access" |

| | | |
|---|---|---|
| | | Concept Plans Pg. 78 - Replace “Lincoln Financial Tower” with “Pond 3A Access”<br>Concept Plans Pg. S-11 - Replace “Lincoln Financial Tower” with “Pond 3A Access”<br>Concept Plans Pg. 11-12, 16-18 - Correction of canal representation and R/W Location representation.<br>Concept Plans Pg. 214-217 - Speed Reduction during TTCP to 45 mph.<br>Concept Plans Pg. 21-76 - Updated Plan / Profile Sheets with revised Utilities<br>Concept Plans Pg. 87-210 - Updated Cross Section Sheets with revised Utilities<br>Concept Plans Pg. S-4 – Added Existing Flashing Beacon |
| RFP, Reference Document 1.3 | 06/10/20 | Updated Reference Document 1.3 Permit Application |
| RFP, Reference Document 2.6 | 06/10/20 | “444444-2-52-01 Reference 2.6 Florida Department of Environmental Protection (FDEP) Draft CERPRA Permit” added |
| RFP Reference Document 4 | 06/10/20 | Updated “444444-2-52-01 Reference 4 CAP” |

This **addendum authorizes** the change to the submittal requirements for the following sections of the RFP for E6M92:

**VII. Technical Proposal Requirements:**

**B. Submittal Requirements:**

**The Technical Proposal shall be submitted electronically.** The Technical Proposal shall be submitted using Form 700-010-21 Low Bid Design-Build Technical Proposal.

The Technical Proposal shall be submitted electronically and attached to a single email. The Department has a 10MB limit on email. Emails that exceed this 10MB email server limit may be rejected by the Department's email server. It is solely the Design Build Firm's responsibility to ensure that the Technical Proposal is received by the Department's server by the due date and time. Bookmarks which provide links to content within the Technical Proposal are allowed. Bookmarks which provide links to information not included within the content of the Technical Proposal shall not be utilized. No macros will be allowed.

The maximum number of pages shall be 2, single-sided, typed pages including text, graphics, tables, charts, and photographs. Double-sided 8½" x 11" sheets will be counted as 2 pages. Larger sheets are prohibited.

**Submit the Technical Proposal to: D6.designbuild@dot.state.fl.us, on, or before, 10:00AM, Thursday, July 9, 2020.**

**VIII. Bid Proposal Requirements.**

**A. Bid Price Proposal:**

**Bid Price Proposals forms shall be submitted electronically.** Bid Price Proposals shall be submitted on the Bid Blank form attached hereto and shall include one lump sum Price for the Project within which the Proposer will complete the Project. The lump sum price shall include all costs for all design, geotechnical surveys, architectural services, engineering services, Design Build Firms quality plan, construction of the Project, and all other work necessary to fully and timely complete that portion of the Project in accordance with the Contract Documents, as well as all job site and home office overhead, and profit, it being understood that payment of that amount for that portion of the Project will be full, complete, and final compensation for the work required to complete that portion of the Project.

**Bid Price proposals forms must be submitted in the forms provided by the Department and shall be submitted electronically in a single email to the following email account:**

**D6.designbuild@dot.state.fl.us, and is due on, or before, 10:00AM, Thursday, July 9, 2020.**

The Subject Line for the email must show: E6M92 Proposal Package - (Insert Design Build Firms Name).
All proposals submitted electronically shall contain a file attachment and be marked as follows:
E6M92 Proposal Package - (Insert Design Build Firms Name).
All documents shall be submitted in portable document format (PDF).

Emails that exceed the 10 MB email server limit may be rejected by the Department's email server. It is solely the Design Build Firm's responsibility to ensure that the bid price proposal forms are received by the Department's server by the due date and time.

The Design-Build Firm with the lowest bid and determined to be responsive who is awarded the contract must also submit the original Bid or Proposal Bond (375-020-34) via US Mail, UPS, or Fed Ex in a sealed package to the address below, by July 23, 2020, by 5:00PM:

Ms. Suzanne Diaz
Florida Department of Transportation
District Six
1000 NW 111th Avenue, Room 6202-B
Miami, FL 33172

The Public Bid Opening Meeting will be conducted on July 9, 2020, at 11:00AM, via GoToMeeting.
Design Build Firms can join the meeting by calling telephone conference number: 1 (872) 240-3212,
Access Code: 147-679-205.

---

You must acknowledge receipt of this **Addendum One** when you submit your bid.

**All other documents of the subject project remain unchanged**.
Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.